



Recommended Practice for
**Commissioning Building
Electrical Systems**

NEIS



Published by
National Electrical
Contractors Association



Table of Contents

- Foreword**v
- 1. Scope**1
 - 1.1 Applications Included1
 - 1.2 Regulatory and Other Requirements1
- 2. Definitions**2
- 3. Commissioning Process**3
 - 3.1 Commissioning Intent3
 - 3.2 Roles and Responsibilities of the Commissioning Authority3
 - 3.3 Commissioning Authority Qualifications4
 - 3.4 Roles and Responsibilities of Other Parties4
- 4. Testing Requirements**6
 - 4.1 Test Equipment6
 - 4.2 Verification and Pre-functional Performance Testing6
 - 4.3 Functional Performance and Condition Monitoring Tests7
 - 4.3.1 *Medium and High Voltage Power Cables (above 600V)*7
 - 4.3.2 *Low Voltage Power Cable (below 600V)*7
 - 4.3.3 *Electrical Feeders and Branch Circuits (600V or below)*7
 - 4.3.4 *Liquid-Filled Transformers*7
 - 4.3.5 *Dry-Type Transformers*8
 - 4.3.6 *Instrument Transformers*8
 - 4.3.7 *Switchgear and Switchboard Assemblies Rated 1200A or Greater*8
 - 4.3.8 *Metal-Enclosed Bus Duct*9
 - 4.3.9 *Motor Control Centers*9
 - 4.3.10 *Medium-Voltage Circuit Breakers*9
 - 4.3.11 *Low-Voltage Air Circuit Breakers*9
 - 4.3.12 *High and Medium-Voltage Air Switches*10
 - 4.3.13 *Protective Relays*10
 - 4.3.14 *Molded-Case Circuit Breakers*10
 - 4.3.15 *Service Ground*10
 - 4.3.16 *Ground-Fault Protection Systems*11
 - 4.3.17 *Panelboards*11
 - 4.3.18 *Receptacles and Devices*11
 - 4.3.19 *Engine Generators*11
 - 4.3.20 *Automatic Transfer Switches*12
 - 4.3.21 *Variable Frequency Drives*12
 - 4.3.22 *Rotating Machinery*12
 - 4.3.23 *Battery Systems*13
 - 4.3.24 *Uninterruptible Power Supply (UPS) System*13
 - 4.3.25 *Lighting*14
 - 4.3.26 *System Testing*15

4.4	Deferred Testing	15
4.5	Seasonal Testing	15
5.	Recording and Documenting Performance	16
5.1	Documentation	16
5.2	Non-conformance Forms	16
6.	O&M Manuals	17
7.	Training	18
Annex A: Test and Measurement Equipment		19
A.1	Vibration Monitoring	19
A.2	Infrared Thermography (IRT)	19
A.3	Insulation Power Factor	19
A.4	Battery Impedance	20
A.5	Breaker Timing	20
A.6	Insulation Resistance	20
Annex B: Reference Standards		21

1. Scope

1.1 Applications Included

This recommended practice describes procedures for commissioning newly installed or retrofitted building electrical systems. It defines the process of commissioning building electrical systems and provides sample guidelines for attaining optimum system performances that conform to design, specifications, and industry-accepted codes and standards.

Only qualified persons familiar with construction and operation of building electrical systems should perform the work described in this publication.

Other *National Electrical Installation Standards* provide additional guidance for installing particular types of electrical products and systems. A complete list of *NEIS* is provided in Annex B.

1.2 Regulatory and Other Requirements

All information in this publication is intended to conform to the National Electrical Code (ANSI/NFPA 70).