

NECA 90

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33



Standard for Commissioning Building Electrical Systems

**ANSI Recirculation Draft ~~Canvass~~ Ballot
August 20240**

National Electrical Installation Standards and *NEIS*
are trademarks of the National Electrical Contractors Association

34 (This Foreword is not a part of the Standard)

35

36 Foreword

37

38 *National Electrical Installation Standards*[™] (*NEIS*[™]) are designed to improve communication among
39 specifiers, purchasers, and suppliers of electrical construction services. They define a minimum baseline
40 of quality and workmanship for installing electrical products and systems. *NEIS*[™] are intended to be
41 referenced in contract documents for electrical construction projects. The following language is
42 recommended:

43

44 Electrical systems shall be commissioned in accordance with NECA 90-2XXX, *Standard for*
45 *Commissioning Building Electrical Systems* (ANSI).

46

47 Use of *NEIS*[™] is voluntary, and the National Electrical Contractors Association (NECA) assumes no
48 obligation or liability to users of this publication. Existence of a Standard shall not preclude any member
49 or non-member of NECA from specifying or using alternate construction methods permitted by
50 applicable regulations.

51

52 This publication is intended to comply with the National Electrical Code (NEC). Because they are quality
53 Standards, *NEIS* may in some instances go beyond the minimum safety requirements of the NEC. It is
54 the responsibility of users of this publication to comply with state and local electrical Codes and Federal
55 and state OSHA safety regulations as well as follow manufacturer installation instructions when installing
56 electrical products and systems.

57

58 Suggestions for revisions and improvements to this Standard are welcome. They should be addressed to:

59

NECA Standards & Safety
3 Bethesda Metro Center, Suite 1100
Bethesda, MD 20814
(301) 657-3110
(301) 215-4500 Fax
www.neca-neis.org
neis@necanet.org

60

61

62

63

64

65

66

67 To purchase *National Electrical Installation Standards*, contact the NECA Order Desk at (301) 215-4504
68 tel, (301) 215-4500 fax, or orderdesk@necanet.org. *NEIS* can also be purchased in .pdf download format
69 at www.neca-neis.org/standards.

70

71 Copyright ©2XXX, National Electrical Contractors Association. All rights reserved. Unauthorized
72 reproduction prohibited.

73

74 *National Electrical Installation Standards*, *NEIS*, and the *NEIS* logo are registered trademarks of the
75 National Electrical Contractors Association. *National Electrical Code* and *NEC* are registered trademarks
76 of the National Fire Protection Association, Quincy, MA.

77

78

79

Table of Contents

80		
81		
82		
83	Foreword
84		
85	1. Scope
86	1.1	Products and Applications Included.....
87	1.2	Products and Applications Excluded.....
88	1.3	Regulatory and Other Requirements
89	1.4	Mandatory Requirements, Permissive Requirements, Quality and Performance
90		Recommendations, Explanatory Material, and Informative Annexes.....
91		
92	2. Definitions
93		
94	3. Safety
95	3.1	General
96	3.2	Safe Work Practices
97	3.3	De-energizing Electrical Equipment
98	3.4	Battery Systems
99	3.4.1	<i>Battery Electrical Safety</i>
100	3.4.2	<i>Electrolyte</i>
101	3.4.3	<i>Hydrogen Gas</i>
102	3.5	Automatic (Remote) Operation
103	3.6	Rotating Machinery
104	3.7	Operating Temperatures
105	3.8	Generator Fuel Systems and Exhaust Gases
106		
107		
108	4. Commissioning Process
109	4.1	Overview
110	4.2	Commissioning Plan (CP).....
111	4.3	Commissioning Authority (CA) Roles and Responsibilities
112	4.4	Electrical Design Engineer Roles and Responsibilities
113	4.5	Contractor Roles and Responsibilities
114	4.5.1	<i>General Contractor Roles and Responsibilities</i>
115	4.5.2	<i>Mechanical Contractor Roles and Responsibilities</i>
116	4.5.3	<i>Electrical Contractor Roles and Responsibilities</i>
117	4.6	Documentation
118		
119	5. Testing Requirements
120	5.1	Test Equipment
121	5.1.1	<i>Calibration</i>
122	5.1.2	<i>Data Logging</i>
123	5.2	Contractor Pre-Startup, Startup, and Post-Startup Procedures.....
124	5.3	Pre-Functional Performance Procedures and Checklists
125	5.4	Functional Performance Procedures
126	5.5	Commissioning Requirements of Electrical Equipment
127	5.5.1	<i>General Electrical Commissioning Requirements</i>
128	5.5.2	<i>Medium and High Voltage Power Cables (above 600V)</i>

129 5.5.3 Low Voltage Power Cable (below 600V)

130 5.5.4 Electrical Feeders and Branch Circuits (600V or below)

131 5.5.5 Liquid-Filled Transformers

132 5.5.6 Dry-Type Transformers

133 5.5.7 Instrument Transformers

134 5.5.8 Switchgear and Switchboard Assemblies Rated 1200A or Greater

135 5.5.9 Metal-Enclosed (Medium-Voltage) Bus and Low-Voltage Busway

136 5.5.10 Motor Control Centers

137 5.5.11 Low-Voltage Motor Starters

138 5.5.12 Medium-Voltage Motor Starters

139 5.5.13 Medium-Voltage Circuit Breakers

140 5.5.14 Medium-Voltage Air Circuit Breakers

141 5.5.15 Medium-Voltage Vacuum Circuit Breakers

142 5.5.16 Medium-Voltage SF₆ (Sulfur Hexafluoride) Circuit Breakers

143 5.5.17 Low-Voltage Air-Insulated and Insulated Case Circuit Breakers

144 5.5.18 Low-Voltage (600V Class) Network Protectors

145 5.5.19 Low Voltage Air Switches.....

146 5.5.20 High and Medium-Voltage Air Switches

147 5.5.21 Protective Relays and Metering Devices.....

148 5.5.22 Molded-Case Circuit Breakers

149 5.5.23 Low-Voltage Power Circuit Breakers

150 5.5.24 Grounding Systems

151 5.5.25 Ground-Fault Protection Systems

152 5.5.26 Panelboards

153 5.5.27 Receptacles and Wiring Devices

154 5.5.28 Engine Generators

155 5.5.29 Automatic Transfer Switches (ATSs)

156 5.5.30 Variable Frequency Drives (VFDs)

157 5.5.31 AC Synchronous Motors and Generators

158 5.5.32 AC Induction Motors and Generators (Alternators)

159 5.5.33 DC Motors and Generators.....

160 5.5.34 Battery Systems

161 5.5.35 Battery Chargers

162 5.5.36 Flooded Lead Acid Batteries

163 5.5.37 VRLA Batteries

164 5.5.38 Uninterruptible Power Supply (UPS) Systems

165 5.5.39 Lighting

166 5.5.40 System Testing

167 5.5.41 Medium and High-Voltage Surge *Arresters* *Protective Devices (SPDs)*

168 5.5.42 Low-Voltage Surge Protective Devices (SPDs)

169 5.5.43 Capacitors

170 5.5.44 Dry-Type Reactors (Shunt and Current-Limiting)

171 5.5.45 Liquid-Filled Reactors (Shunt and Current-Limiting)

172 5.6 Deferred and Seasonal Testing

173

174 **6. Recording and Documenting Performance.....**

175 6.1 Documentation

176 6.2 Non-Conformance Items

177

178 **7. Operating and Maintenance (O&M) Manuals**

179
180 **8. Training**.....
181
182 **9. Annex A: Electrical Testing Procedures**
183
184 **10. Annex B: Reference Standards**
185
186
187
188

189 1. Scope

190

191 1.1 Products and Applications Included

192

193 This Standard describes installation procedures for start-up, testing, and commissioning newly installed or
194 retrofitted building electrical systems, equipment, and components. It defines the commissioning process
195 and provides sample guidelines for attaining optimum system performance that conform to design,
196 specification, and industry accepted Codes and Standards.

197

198 This Standard addresses those commissioning activities that typically involve the Electrical Contractor
199 and that are completed during and after the construction phase. The commissioning process also involves
200 activities that are beyond the scope of this Standard.

201

202

203 1.2 Products and Applications Excluded

204

205 This Standard is not intended to cover specific commissioning processes for every type of electrical
206 system, equipment, or component. Other *NEIS* documents that include commissioning and testing
207 requirements for electrical systems, equipment, and components are included as references and are listed
208 in Annex B.

209

210 In addition, this Standard does not cover:

- 211 • Procedures for commissioning systems such as fire alarm systems, telecommunications networks,
212 closed circuit television (CCTV) systems, access control systems, and other limited energy
213 systems.
- 214 • Testing of specialty equipment and systems, such as transformers, wiring, and line isolation
215 monitors installed as part of isolated power systems for wet locations in healthcare facilities.
- 216 • Commissioning and acceptance testing required in accordance with applicable national, state, and
217 local Codes and regulations for life safety systems, emergency systems, and critical operations
218 power systems (COPS) in addition to the generic commissioning and acceptance testing required
219 by this Standard.
- 220 • On-going commissioning and/or maintenance testing required by applicable national, state, and
221 local Codes and regulations for specific applications and systems, such as healthcare facilities and
222 emergency systems.

223

224

225 1.3 Regulatory and Other Requirements

226

227 All information in this publication is intended to conform to the National Electrical Code (ANSI/NFPA
228 70). Installers shall follow the NEC, applicable state and local Codes, manufacturer instructions, and
229 contract documents when commissioning building electrical systems.

230

231 Only qualified persons as defined in the NEC familiar with the commissioning of building electrical
232 systems shall perform the technical work described in this publication. Administrative functions such as
233 receiving, handling, and storing required in Section 4, and other tasks shall be performed under the
234 supervision of a qualified person. All work shall be performed in accordance with NFPA 70E, Standard
235 for Electrical Safety in the Workplace.

236

237 General requirements for installing electrical products and systems are described in NECA 1, Standard
238 Practices for Good Workmanship in Electrical Construction (ANSI). Other NEIS provide additional
239 guidance for installing particular types of electrical products and systems. A complete list of NEIS is
240 provided in Annex B.

241

242

243 **1.4 Mandatory Requirements, Permissive Requirements, Quality and Performance** 244 **Recommendations, Explanatory Material, and Informative Annexes**

245

246 Mandatory requirements in manufacturer instructions, Codes, or other mandatory Standards that may or
247 may not be adopted into law are those that identify actions that are specifically required or prohibited and
248 are characterized in this Standard by the use of the terms “must” or “must not,” “shall” or “shall not,” or
249 “may not,” or “are not permitted,” or “are required,” or by the use of positive phrasing of mandatory
250 requirements. Examples of mandatory requirements may equally take the form of, “equipment must be
251 protected . . .,” “equipment shall be protected . . .,” or “protect equipment . . .,” with the latter
252 interpreted (understood) as “(it is necessary to) protect equipment . . .”

253

254 Permissive requirements of manufacturer instructions, Codes, or other mandatory Standards that may or
255 may not be adopted into law are those that identify actions that are allowed but not required or are
256 normally used to describe options or alternative means and methods and are characterized in this Standard
257 by the use of the terms “may,” or “are permitted,” or “are not required.”

258

259 Quality and performance instructions identify actions that are recommended or not recommended to
260 improve the overall quality or performance of the installation and are characterized in this Standard by the
261 use of the terms “should” or “should not.”

262

263 Explanatory material, such as references to other Codes, Standards, documents, references to related
264 sections of this Standard, information related to another Code, Standard, or document, and supplemental
265 application and design information and data, is included throughout this Standard to expand the
266 understanding of mandatory requirements, permissive requirements, and quality and performance
267 instructions. Such explanatory material is included for information only and is identified by the use of the
268 term “NOTE,” or by the use of italicized text.

269

270 Non-mandatory information and other reference Standards or documents relative to the application and
271 use of materials, equipment, and systems covered by this Standard are provided in informative annexes.
272 Informative annexes are not part of the enforceable requirements of this Standard but are included for
273 information purposes only.

274

275

276 **2. Definitions**

277

278 **Acceptable Performance.** Performance of systems, sub-systems, equipment, and components that
279 meets specified design performance parameters under actual load, operational, and environmental
280 conditions, and responds to changing conditions and parameters appropriately, as expected, and as
281 specified.

282

283 **Acceptance Phase.** Phase of construction after startup and initial checkout when functional
284 performance tests, operation and maintenance (O&M) documentation review, and training occur.

285

286 **Approval.** Acceptance that a piece of equipment or system has been properly installed and is
287 functioning in the tested modes according to the contract documents.

288

289 **Architect / Engineer (A/E).** The prime consultants who comprise the design team, generally the
290 Architect, HVAC mechanical designer/engineer, the control system engineer/designer, and the electrical
291 designer/engineer.

292

293 **Basis of Design (BOD).** A document that records the design criteria and assumptions upon which the
294 design is based.

295

296 **Commissioning.** A systematic process for verifying that building electrical systems perform in
297 accordance with the design intent and the owner's operational requirements.

298

299 **Commissioning Authority (CA).** Individual or company responsible for developing and coordinating
300 the execution of a Commissioning Plan (CP), observing and documenting performance, and ensuring that
301 building systems and equipment function in accordance with the design intent and the owner's operational
302 requirements.

303

304 **Commissioning Plan (CP).** A document that outlines the organization, scheduling, coordination, and
305 allocation of resources and documentation for the overall commissioning process from the construction
306 phase through the warranty period.

307

308 **Commissioning Team.** Working group made up of representatives from the Architect/Engineer (A/E),
309 general contractor, sub-contractors, specialty manufacturers, suppliers, and the owner as required for
310 implementation of the CP.

311

312 **Contract Documents.** Documents binding on parties involved in the completion of the Project
313 (contracts, amendments, drawings, specifications, contract modifications or change orders, and CP).

314

315 **Contractor.** The general contractor or their authorized representative.

316

317 **Deferred Functional Tests.** Functional tests that are performed after substantial completion due to
318 partial occupancy, seasonal loading requirements, design, or other site conditions that prevent tests from
319 being performed prior to substantial completion.

320

321 **Deficiency.** A condition in the installation or function of a component, piece of equipment, or system
322 that is not in compliance with the contract documents.

323

324 **Design Intent.** A narrative description of systems and equipment and their intended modes and

325 sequences of operation as documented in the project documents, drawings and specifications.

326

327 **Factory Testing.** Testing of equipment at the factory by factory personnel, with an owner's
328 representative present if deemed necessary by the owner.

329

330 **Functional Performance Tests.** A full range of checks and tests carried out to determine if all
331 systems, sub-systems, equipment, and components function in accordance with the design intent.
332 Systems are tested under various modes of operation, such as low load levels, high load levels,
333 component failures, unoccupied periods, varying outside air temperatures, fire alarm activation, and
334 power failure. Functional Performance Tests are performed after start-ups and Pre-Functional Checklists
335 are complete.

336

337 **Integrated System Test.** A full range of checks and tests carried out to determine if systems that are
338 integrated together and are dependent upon other systems for proper operation function and interact in
339 accordance with the design intent. Systems are tested under various modes of operation, such as during
340 low load levels, high load levels, component failures, unoccupied periods, varying outside air
341 temperatures, fire alarm activation, and power failure. Integrated System Tests are performed after
342 Functional Performance Tests are complete and prior to Substantial Completion.

343

344 **Method of Procedure (MOP).** A script that is normally prepared for working on critical systems and
345 equipment that details all elements of the work to be performed, typically in a checklist format, and
346 includes spaces for dates and times of critical steps, and for authorization and signatures of responsible
347 parties. Elements typically incorporated into an MOP includes safety requirements, staffing
348 requirements, tool inventories, lists of materials, parts, and supplies needed, weather/environmental
349 factors, notification of interested, involved, and affected parties, back-out plans, emergency responses,
350 and the specific step-by-step sequence of tasks involved, among others.

351

352 **Non-Compliance.** See Deficiency.

353

354 **Non-Conformance.** See Deficiency.

355

356 **Owner's Project Requirements.** Documentation of the primary thought processes and assumptions
357 behind design decisions and that describes the systems, components, conditions, and methods chosen to
358 meet the Design Intent.

359

360 **Phased Commissioning.** Commissioning that is completed in phases (by system, by area, or by floors,
361 for example) due to the complexity of the project, size of the structure, or other scheduling issues, in order
362 minimize total construction time.

363

364 **Pre-Functional Procedures.** A full range of inspections and checks of material and components that
365 verify proper installation of equipment (e.g., anchor bolts tightened, grounding connections complete,
366 conductors terminated, connections torqued, compartments cleaned, and panels and covers installed, for
367 example). Pre-functional procedures, checks and tests, are completed before Functional tests. Pre-
368 functional procedures are typically documented in a checklist format, and typically include manufacturer
369 start-up checklists.

370

371 **Start-up.** Activities where equipment is initially energized, operated, and tested. Start-up is completed
372 prior to Functional Performance Tests.

373

374 **Test Requirements.** Requirements specifying the systems, operating modes, and functions that must

375 be tested.

376

377 **Verification.** The full range of checks and tests carried out to determine if all components, sub-systems,
378 systems, and interfaces between systems operate in accordance with the design intent and owner's
379 requirements, including all modes and sequences of control operation, interlocks and conditional control
380 responses, and specified responses to abnormal or emergency conditions.

381

382 **Warranty Period.** Time period for equipment, parts, and/or labor for the entire project, including
383 individual equipment components and optional extended warranties that are included in the project,
384 during which the Contractor makes repairs, replacements, or adjustments to the Contractor's work with no
385 additional cost to the owner. Warranty begins at the time of Substantial Completion and typically extends
386 for a minimum of one year, unless specifically noted otherwise in the Contract Documents and accepted
387 submittals.

388

389

390 **3. Safety**

391

392 **3.1 General**

393

394 *NOTE: Many tests on electrical equipment involve the use of high test voltages and currents that are life*
395 *hazards to personnel and are capable of damaging or destroying the equipment under test. Institute and*
396 *practice safety rules to prevent injury to personnel who are performing the tests and others who might be*
397 *exposed to hazards. Use test procedures designed to ensure that no intentional damage to equipment will*
398 *result from the testing process.*

399

400 Commissioning electrical equipment includes inspecting and testing equipment during its operation.
401 Hazards exist as an unavoidable characteristic of operating and testing electrical equipment. While the
402 hazard remains, risk can be mitigated through good engineering design, proper work practices, and the
403 proper use of protective equipment.

404

405 Electrical equipment hazards include electric shock (energized equipment, stored energy in batteries and
406 capacitors, multiple sources of electricity), toxic chemicals (electrolyte and hydrogen from batteries,
407 engine-generator oil and coolant), asphyxiation (engine-generator exhaust fumes, products of
408 combustion), explosion (hydrogen from batteries, fuels from engine-generators, arc-blast), rotating
409 machinery (motors and engine-generators), corrosive liquids (battery electrolyte), corrosive vapors
410 (cracked or leaky batteries), fire and explosion hazard (hydrogen gas generated during battery charging
411 cycles, fuels for engine-generators), hazardous fumes or vapors (products of combustion due to fire),
412 confined spaces (manholes), and thermal burns (engine-generator components, batteries, products of
413 combustion, arc-blast), among others.

414

415 Prior to commissioning equipment, read all related installation, operation, and owner's manuals to
416 become familiar with the equipment and with the hazards specific to the equipment. Read all related
417 safety instructions and carefully observe all instructions, warnings, and precautions in this Standard and in
418 the equipment manufacturer instructions. Observe all safety warning labels on equipment.

419

420 Individuals performing tests and inspections shall be capable of working in a safe manner and with
421 complete knowledge of the hazards and methods of mitigating the risks involved.

422

423 Safety practices shall include, but are not limited to, the following requirements:

424

- All applicable provisions of the Occupational Safety and Health Act, particularly OSHA 29CFR

- 425 1910
- 426 • ANSI/NFPA 70E, Standard for Electrical Safety [in the Requirements for Employee Workplaces](#)
 - 427 • Accident Prevention Manual for Industrial Operations, National Safety Council
 - 428 • Manufacturer instructions.
 - 429 • Applicable state and local safety operating procedures
 - 430 • Owner's safety practices

431

432 The following are examples of industry-recognized procedures to follow when commissioning electrical
433 equipment:

- 434 • Conduct a hazard identification and risk analysis prior to any work on electrical equipment. The
435 risk assessment shall be applicable to the specific task to be performed, and shall determine the
436 appropriate level of personal protective equipment (PPE) to be worn while performing the task.
- 437 • Follow manufacturer instructions and recommendations for electrically isolating electrical
438 equipment and components.
- 439 • Check electrical equipment and components for AC and DC voltages to ensure that equipment is
440 electrically safe before performing any inspections, testing, or commissioning.
- 441 • Open all external disconnects or circuit breakers to completely isolate equipment from all AC and
442 DC power sources.
- 443 • Open DC circuit breakers to completely isolate equipment from batteries.
- 444 • Check capacitors for voltage and discharge. Wait a minimum of five minutes for capacitors to
445 discharge before entering electrical equipment cabinets.

446

447 Keep cabinet and access doors secured when not working inside electrical equipment to ensure proper
448 cooling airflow and to protect personnel from dangerous voltages inside equipment. Ensure that doors
449 cannot create a hazard when open due to door swing or limited work space around equipment. *NOTE:*
450 *Some equipment may have lock-bars for compartment doors or removable doors for this purpose.*

451

452

453 3.2 Safe Work Practices

454

455 Perform preliminary inspections and tests prior to beginning work to determine existing conditions.
456 Check existing conditions against available record documents. Resolve discrepancies between installed
457 conditions and electrical drawings. Have drawings corrected, if required. Provide warning labels on
458 equipment and cables where necessary to indicate unexpected and potentially hazardous conditions.

459

460 Visually verify conductor routing through all raceways, manholes, and vaults. Visually verify all
461 conductor connections to equipment. Confirm that supply and load conductors are connected properly to
462 equipment. Keep in mind that transposed conductors may be connected to different terminals than
463 expected.

464

465 Maintain as much distance as practical from equipment and devices that may arc during operation or
466 handling, but not less than the arc flash protection boundary specified in NFPA 70E.

467

468 Use appropriate Personal Protective Equipment (PPE) and established safety procedures when working on
469 or near energized electrical equipment or equipment that has not been de-energized, tested, grounded, and
470 tagged in accordance with NFPA 70E. Wear appropriate personal protective equipment in accordance
471 with the Arc Flash Hazard level of the equipment.

472

473 Use insulated hand tools when working on or around energized equipment. Use only tools that are
474 properly rated for the energy present. Maintain tool inventories to ensure that all tools are accounted for

475 prior to energizing equipment. Carefully inspect the work area and remove any tools and objects left
476 inside before energizing equipment.

477

478 Operate electrical equipment only when all guards, barriers, doors, covers, and panels are in place and
479 secured. Install all devices, doors, covers, and panels before energizing. Do not tamper with or defeat
480 safeties or interlocks. Do not make any modifications to the equipment or operate the system with
481 interlocks or safety barriers removed.

482

483 When performing tests, service, or maintenance on any part of energized equipment, service personnel
484 and test equipment should be standing on rubber insulating mats. Do not wear damp clothing
485 (particularly wet shoes) or allow skin to be damp when working on or near electrical equipment.

486

487 During normal operation, hazardous voltages are present on control circuits, potential transformers (PTs),
488 current transformers (CTs), and terminal strips. PT and CT secondary circuits are capable of generating
489 lethal voltages and currents with the primary circuits energized. Do not open-circuit current transformer
490 secondary circuits while equipment is energized, as open-circuited CT terminals can develop voltage near
491 the nominal system voltage and are a significant shock hazard. Follow standard safety precautions, such
492 as removing PT fuses and shorting CT secondaries.

493

494 All workers in manholes must have an OSHA Certification for Confined Space Access. Crews working
495 in confined spaces shall consist of two or more persons with at least one remaining outside the confined
496 space at all times. Maintain a personnel retrieval system at the site.

497

498 Test manholes and unventilated vaults for combustible or flammable gases and for oxygen deficiency
499 before entry. Where combustible or flammable gases are detected, ventilate the work area to safe levels
500 before entering. Provide continuous monitoring of occupied manholes and vaults for gasses and oxygen
501 deficiency.

502

503 Provide continuous, mechanically supplied fresh air to manholes and vaults when occupied. Provide
504 blowers to force fresh air into manholes or confined areas where free movement or circulation of air is
505 obstructed. Ensure air flow from manholes or confined areas is properly ventilated at duct entrances into
506 buildings.

507

508 Ensure adequate ventilation where open flames must be used in manholes or vaults.

509

510 Ensure that there is access to a fire extinguisher with an ABC or BC rating, or as recommended for
511 electrical fires by the local Fire Code or an authorized agency.

512

513

514 **3.3 De-energizing Electrical Equipment**

515

516 Consider all ungrounded and grounded metal parts of equipment and devices to be energized at the
517 highest voltage to which they are exposed unless they are de-energized, tested, locked, and red tagged in
518 accordance with OSHA requirements. Electrical equipment may have multiple sources of power. Expect
519 hazardous voltages in all interconnecting components and conductors. Keep in mind that high voltage
520 DC is always present because of the nature of stored energy in battery systems.

521

522 Do not work on energized conductors or equipment (except batteries, which are always energized). Using
523 established safety procedures, guard energized conductors and equipment in close proximity to work.

524

525 Render equipment electrically safe. De-energize as many loads as is practical before performing any
526 switching procedures. Transfer loads to alternate sources of power, when possible. Follow manufacturer
527 instructions for electrically isolating equipment. Open all external disconnects or circuit breakers to
528 completely isolate all power sources, including batteries.

529
530 Verify that circuit breakers and switches are open by testing to confirm that desired cables and equipment
531 are de-energized. Use electrical testing equipment rated for the operating voltage of the system. Test
532 voltage sensing equipment on a known, energized source immediately before and after testing the
533 equipment to be tested to ensure that voltage sensing equipment is operating properly.

534
535 Follow lock-out/tag-out (LOTO) procedures. After compartments are opened, test for the presence of
536 voltage and apply locks and tags in accordance with NFPA 70E and OSHA. Secure source circuit
537 breakers and switches with locks and tags in accordance with NFPA 70E. Leave locks and tags in place
538 until the work is completed and the equipment is ready to be put into service.

539
540 Attach Listed personal protective grounds on conductors and equipment that are sufficient for the
541 available short circuit current from the supplier. For conductors equipped with reconnectable
542 terminations, disconnect conductors from terminal bushings and park on stands. Follow manufacturer
543 instructions for grounding conductors with reconnectable terminations. Connect personal protective
544 grounds to the line terminals of the main circuit breaker or main lugs, to the neutral terminal bus bar, if so
545 equipped, and to the grounding terminal of equipment.

546
547

548 **3.4 Battery Systems**

549
550 Follow manufacturer installation, servicing, and maintenance instructions, or follow industry Standards.

551
552 *NOTE: A battery is a source of stored energy. Voltage is always present in each battery string.*
553 *Batteries connected in series and strings connected in parallel can have high voltage and current*
554 *capacities. Opening the battery disconnecting means does not de-energize the voltage within the battery*
555 *string itself. Shock potential is greatest at the terminals of a battery. Battery voltages can cause injury*
556 *and death if contact is made between positive and negative terminals or conductors. Take care to avoid*
557 *contact with both battery terminals at the same time.*

558
559 *NOTE: Contact of eyes and mucus membranes with electrolyte can cause severe burns and blindness.*
560 *During charging, batteries can produce and/or emit a highly flammable mixture of hydrogen and oxygen*
561 *which can be explosive in high concentrations.*

562
563 Appropriate safety equipment shall be used as deemed necessary by a risk assessment of the task being
564 performed while in battery rooms or when working near batteries. Personal protective equipment (PPE)
565 required for working on battery systems is identified in NFPA 70E. Remove all jewelry before servicing
566 equipment. Goggles shall always be worn. Other PPE typically includes, but is not limited to, face
567 shields, safety glasses with side shields and splash protection, head protection appropriate for
568 environments with electrical hazards, insulated rubber gloves and sleeves suitable for the voltage class of
569 equipment present, acid- or alkali-resistant gloves, protective or impermeable aprons, and acid- or alkali-
570 resistant boots or overshoes.

571
572 Prior to work on a battery with free-flowing liquid electrolyte (such as vented lead-acid or vented nickel-
573 cadmium batteries), verify that a complete spill clean-up kit that is appropriate for the hazard and risk is
574 readily available in the room. Sufficient neutralizing agent shall be readily available to neutralize, at a

575 minimum, the total electrolyte in a single cell or multi-cell container, to a pH of 5-9. Spill prevention,
576 abatement methods, and equipment shall be in accordance with IEEE Std. 1578 – Recommended Practice
577 for Stationary Battery Spill Containment and Management.

578

579 Egress from the work area shall be unobstructed.

580

581 Verify that fire suppression systems are:

- 582 • Suitable for use in electrical fires per the equipment safety data sheets
- 583 • Suitable for use with any chemicals likely to be released if the battery is consumed in flame
- 584 • Tested to be operational with the date of the most recent test readily available

585

586 Keep in mind that the use of CO₂ Class C fire extinguishers may not be permitted due to the potential of
587 thermal shock and cracking battery containers, and the hazard of oxygen depletion within the space.

588 Local Codes typically identify the permissible fire protection methods.

589

590 If an emergency eye wash or quick-drench shower are located near the battery area they must be
591 maintained in accordance with manufacturer recommendations and Federal, state, and local regulations
592 pertaining to such equipment.

593

594 Do not attempt to disassemble or in any way handle batteries that are, or have recently been, involved in
595 fire. Batteries can explode or release hazardous substances when exposed to extreme heat or fire.

596

597

598 **3.4.1 Battery Electrical Safety**

599

600 Adhere to the following practices when working around battery systems or other stored energy devices to
601 protect against electric shock or other hazards:

- 602 • Do not place tools or other conductive objects on battery cells, racks, or tiers
- 603 • Use insulated tools to protect against shorting of cells
- 604 • Use PPE appropriate for the task to be completed based on the hazard analysis and risk
605 assessment performed prior to the work
- 606 • Discharge static electricity from the body before touching cell terminal posts by first touching a
607 grounded surface in the vicinity of the batteries but away from the cells and flame arrestors

608

609 Disconnect the charging source prior to connecting or disconnecting battery terminals.

610

611 Verify the battery grounding method prior to working on the battery system. Inspect batteries for
612 inadvertent grounding during installation and maintenance. Remove inadvertent grounds to reduce the
613 likelihood of shock. Disconnect battery ground connections only in accordance with the manufacturer
614 instructions.

615

616

617 **3.4.2 Electrolyte**

618

619 *NOTE: Electrolyte in contact with the eyes or mucus membranes can cause severe burns or blindness. If*
620 *electrolyte comes in contact with eyes, nose, or mouth, flush the affected area immediately with copious*
621 *amounts of water and obtain medical assistance immediately. Electrolyte in contact with skin can cause*
622 *an allergic reaction in some people. Electrolyte is about the same level of hazard as vinegar or lemon*
623 *juice. If electrolyte comes in contact with skin, wash the area thoroughly with soap and water. Refer to*
624 *battery safety data sheets shipped with the system for further information.*

625
626 Wear personal protective equipment, including eye and skin protection, when performing tasks that
627 potentially expose a worker to electrolyte.

628
629 Follow manufacturer instructions to neutralize an electrolyte leak or spill. *NOTE: Some chemicals can*
630 *cause damage to the cell container. A common neutralizer for lead-acid electrolyte is a bicarbonate of*
631 *soda solution in a concentration of one pound per gallon of water to neutralize acid spilled on clothing or*
632 *material. Apply the solution until bubbling stops, and then rinse with clear water.*

633
634 *NOTE: Guidelines for the design of electrolyte spill protection and response to electrolyte spills can be*
635 *found in IEEE 1578, Recommended Practice for Stationary Battery Electrolyte Spill Containment and*
636 *Management. Guidelines for personal protective equipment around batteries can be found in the*
637 *manufacturer safety data sheets, in IEEE Standards applicable to the battery technology, or in NFPA*
638 *70E, Standard for Electrical Safety in the Workplace.*

639
640

641 **3.4.3 Hydrogen Gas**

642
643 *NOTE: As batteries charge, hydrogen, which is a colorless, odorless, and tasteless gas that is non-toxic*
644 *under normal conditions, may be released. Hydrogen is the smallest, the lightest, and one of the most*
645 *common molecules in the known universe. Hydrogen diffuses rapidly with the slightest amount of air*
646 *movement. Hydrogen is extremely difficult to contain and can even penetrate concrete blocks. Hydrogen*
647 *will always tend to rise to the highest level of a confined space, rising two times faster than helium and*
648 *six times faster than natural gas. Hydrogen is a severe fire hazard when exposed to heat, flame, or*
649 *oxidizer, and can become explosive in high enough concentrations. The flammability range for hydrogen*
650 *is very wide with a lower flammability limit of 4.1 percent by volume and the upper limit of 74.2 percent.*

651
652 Verify that battery rooms and compartments with lead-acid batteries are adequately ventilated to prevent
653 hydrogen levels from exceeding levels specified in local Codes. *NOTE: Fire Codes typically stipulate a*
654 *one percent concentration by volume of the space. Gassing rates can be affected by temperature, air*
655 *pressure, the battery construction, and the amount of charge current passing through cells. Not all gas*
656 *generated in a battery escapes to the atmosphere. Calculations for hydrogen ventilation shall be*
657 *performed by a qualified person based upon data provided by the battery manufacturer for the battery*
658 *under specified conditions. Additional ventilation may be required during an activation charging cycle*
659 *or other charging regimens.*

660
661 Open flames, sparks, hot plates, smoking, or any other ignition sources are prohibited near batteries, gas
662 ventilation paths, or anywhere that hydrogen can accumulate. Discharge static electricity from the body
663 before touching batteries by first touching a grounded metal surface.

664
665

666 **3.5 Automatic (Remote) Operation**

667
668 *NOTE: Equipment that is controlled remotely or automatically may start and operate unexpectedly.*
669 *Accidental or unexpected starting can cause severe injury or death.*

670
671 Protect against accidental energization of automatic or remotely controlled equipment by identifying,
672 opening, locking, and tagging starting devices. Do not connect controls or control power to electrical
673 equipment until the installation is complete and the equipment is ready to operate. Become familiar with
674 equipment control schemes prior to commissioning.

675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724

3.6 Rotating Machinery

Ensure that all panels, doors and covers are attached and closed whenever rotating equipment, such as flywheels, motors, and engine-generators, are operating. Operate equipment only when all guards, barriers, screens, and electrical enclosures are in place. Make sure that fasteners on equipment are secure. Ensure that supports and clamps are tight.

If adjustments must be made while equipment is running with protective guards and barriers removed, use extreme caution around moving parts.

Do not wear loose clothing or jewelry in the vicinity of moving parts, or while working on electrical equipment. *NOTE: Loose clothing, jewelry, hands, and hair can become caught in moving parts. Jewelry can short out electrical contacts and cause shock, burns, or death.*

3.7 Operating Temperatures

NOTE: Some electrical equipment components can become extremely hot during operation and remain hot for a period of time after shutting down, such as motors, power electronics, and engines of engine-generators. Hot equipment and components can cause severe injury or death.

Avoid contact with hot components and parts. Do not work on equipment until it cools down. Use extreme caution when working around hot electrical equipment is necessary to make adjustments while equipment is running.

3.8 Generator Fuel Systems and Exhaust Gases

NOTE: Generator fuels and fuel vapors are flammable and highly explosive. Servicing the generator fuel system can result in an explosion or flash fire that can cause severe injury or death.

Do not operate the generator if the smell of fuel is present or other explosive conditions exist. Never add fuel manually to a sub-base fuel tank or day tank while the engine is running. *NOTE: Spilled fuel may ignite on contact with hot parts or components, or from sparks.* When checking, draining, or adding diesel fuel to a generator, take care not to ingest, breathe the fumes, or otherwise make contact with the fuel.

Do not smoke or permit flames, cigarettes, pilot lights, sparks, arcing equipment, or other sources of ignition near the carburetor or injectors, fuel line, fuel filter, fuel or injection pump, fuel tank, or other potential sources of spilled fuels or fuel vapors.

Do not operate the generator with the air filter or air cleaner cover removed. *NOTE: A sudden backfire can cause severe injury or death.*

NOTE: Exhaust gases contain carbon monoxide, which is odorless, colorless, and poisonous. Avoid breathing exhaust fumes when working on or near a generator. Carbon monoxide can cause light-headedness, throbbing in the temples, headache, dizziness, stomachache, severe nausea, vomiting, weakness, sleepiness, fatigue, muscular twitching, inability to concentrate or speak clearly, fainting,

725 *unconsciousness, or death.*

726

727 If anyone experiences any symptoms of carbon monoxide poisoning, evacuate the area, immediately
728 move to fresh air, and stay active. Do not sit, lie down, or fall asleep. Alert others to the possibility of
729 carbon monoxide poisoning. Seek medical attention if the condition of affected persons does not improve
730 within minutes of breathing fresh air. Shut down the generator and do not operate the generator until it
731 has been inspected and repaired as needed. If symptoms persist, seek medical attention immediately.

732

733

734 **4. Commissioning Process**

735

736 **4.1 Overview**

737

738 The intention of commissioning is to ensure that all electrical equipment, components, sub-systems, and
739 systems are installed according to the contract documents, drawings and specifications, to manufacturer
740 instructions, and to industry-accepted Standards, and that installed electrical equipment, components, sub-
741 systems, and systems, are complete, and that they receive adequate operational checkout and detailed
742 testing, calibration, and adjustment by the installing contractor.

743

744 *NOTE: It is not the intent of the commissioning process or this Standard to duplicate efforts or to require*
745 *the contractor or any subcontractor to perform any check or test twice. Checks and testing are expected*
746 *to occur once in the normal sequence of installation and checkout, if appropriate coordination has*
747 *occurred, allowing the owner and the Commissioning Authority (CA) to witness and document*
748 *installation and testing.*

749

750 Commissioning of building electrical systems is a systematic process of ensuring that all procedures,
751 checks, and testing is rigorously executed and documented, and that all systems perform in accordance
752 with the design intent and the owner's requirements. This is achieved by verifying that the performance
753 meets or exceeds the designer's intent as documented in the project drawings and specifications.

754

755 The electrical commissioning process integrates the traditionally separate functions of equipment startup,
756 control system calibration, testing and balancing (including electrical load balancing as required in the
757 NEC), functional performance testing, system documentation, and training. Commissioning may include
758 deferred and/or seasonal tests as approved by the owner.

759

760 *NOTE: The commissioning process does not reduce the responsibility of the installing contractors to*
761 *provide a complete, finished, and fully functioning product. In general, the CA does not have the*
762 *authority to provide direction to contractors. Any issues arising during commissioning which impact*
763 *schedules, costs, or contractual obligations must be addressed by the owner for resolution.*

764

765 The documented procedures which comprise the construction-phase commissioning process generally
766 include the following:

767

768

769

770

771

772

773

774

- Pre-Commissioning that consists of normally specified checks and testing, and wiring and controls point-to-point verification completed by the respective contractor or subcontractor before the formal commissioning process begins.
- Pre-Functional Procedures (PFPs) that consist of a series of field observations conducted during the installation of equipment yet to be commissioned to verify that equipment and systems are installed in accordance with contract documents and are ready for startup.
- Pre-Startup Testing that consists of the typically-specified Contractor testing, such as meter testing of electrical equipment.

- 775 • Equipment Startup Procedures that ensure that startup is performed in accordance with the
776 manufacturer-recommended procedures, and that those startup activities and data are documented
777 for future reference.
- 778 • Contractor Post-Startup Testing that consists of typical contractor testing activities as required by
779 contract documents that occur after startup and before Functional Performance Procedures, such
780 as debugging.
- 781 • Functional Performance Procedures (FPPs) that consist of determining if equipment and systems
782 operate in accordance with the design intent and contract documents.
- 783 • Operation and Maintenance Manuals that will be reviewed for both content and organization.
784 *NOTE: The objective of the review process is to provide the owner with useful, complete,*
785 *project-specific information needed to successfully operate and maintain the facility after*
786 *turnover.*
- 787 • Operator Training that will be provided and coordinated by the contractor and overseen by the
788 owner to help ensure that operating and maintenance staff is adequately prepared to operate and
789 maintain the facility at turnover.

790

791 *NOTE: The project is generally not considered to be substantially complete until the conclusion of*
792 *functional performance procedures as defined in the CP. The CA reviews and coordinates the training*
793 *provided by the contractors and verifies that it was completed. Deferred or seasonal testing is*
794 *conducted as specified or required.*

795

796

797 **4.2 Commissioning Plan (CP)**

798

799 The Commissioning Plan (CP) is typically developed and coordinated by the Commissioning Authority
800 (CA) and is typically provided as part of the contract bid documents. The CP provides guidance for the
801 execution of commissioning activities, and provides a broad outline of the entire commissioning process.

802

803 The CP typically details the commissioning activities during design and construction, along with
804 occupancy and operational commissioning activities and the roles and responsibilities of all
805 commissioning team members, by name, firm, and trade specialty, for performance of each
806 commissioning task. Commissioning team members include the CA, owner, general contractor, design
807 engineers or Architect/Engineer (A/E), and mechanical and electrical subcontractors.

808

809 The CP is a dynamic document that is continuously updated throughout the design, construction, and
810 warranty phases of the project.

811

812 Commissioning of building electrical systems requires full cooperation and coordination between all
813 trades. The roles and responsibilities of the CA, the electrical design engineer, general contractor,
814 mechanical contractor, and electrical contractor are typically delineated in the contract documents and in
815 the CP.

816

817

818 **4.3 Commissioning Authority (CA) Roles and Responsibilities**

819

820 The Commissioning Authority (CA) is responsible for coordinating and directing commissioning
821 activities in a logical, sequential, and efficient manner, using standard forms and centralized
822 documentation.

823

824 The CA is responsible for developing the CP (typically during the design phase) and for coordinating the

825 execution of the CP, such as observing and documenting equipment and system performance, and
826 ensuring that electrical systems are functioning in accordance with the documented design intent and with
827 contract documents. The CA does not have authority to approve materials, methods, and systems, but can
828 recommend their approval to the owner, project manager, or contracting officer.

829

830 The CA is the primary point of responsibility to inform the contractor, subcontractors, owner, and
831 design team on the status, integration, and performance of mechanical and electrical systems within the
832 facility. The CA conducts an initial commissioning meeting where the commissioning process is
833 reviewed with the members, and conducts additional meetings throughout construction, with necessary
834 parties attending, to plan, coordinate, and schedule future activities, and to resolve problems.

835

836 The CA is typically a knowledgeable industry professional, such as an electrical contractor, an electrical
837 design engineer, or a third party contracted to perform the commissioning process. In general, the CA is
838 an independent third-party agency working under a separate contract and reporting directly to the owner.

839

840 Tasks typically completed by the CA include, but are not limited to:

- 841 • Obtaining and reviewing design and construction documents to determine the overall design
842 intent and the required system configurations.
- 843 • Preparing an initial CP, including an overall testing plan and schedule for electrical systems that
844 lists the equipment, modes to be tested, the scheduling requirements of testing, and the parties
845 conducting the tests.
- 846 • Coordinating scheduled commissioning activities with the overall project schedule, incorporating
847 commissioning tests and tasks into the master construction schedule, maintaining the CP, and
848 updating the schedule.
- 849 • Collaborating with each contractor and subcontractor to develop startup plans, project-
850 specific functional performance test procedures, checklists, and test forms for electrical
851 equipment, components, and systems scheduled for commissioning.
- 852 • Periodically reviewing updated as-built documentation for accuracy and completeness, and
853 verifying that documents are being kept up-to-date.
- 854 • Developing and distributing standard forms used by the commissioning team, including
855 startup documentation formats and construction checklists to be completed during the
856 installation and startup process, for consistency of approach, and the type of information
857 recorded.
- 858 • Performing site visits, as necessary, to observe equipment, component and system
859 installations.
- 860 • Reviewing submittals and shop drawings for installation criteria and construction details as they
861 support and define system features.
- 862 • Coordinating, witnessing, and verifying acceptability of functional performance tests performed
863 by the installing contractors. Coordinating re-testing as necessary until satisfactory performance
864 is achieved.
- 865 • Notifying the owner's representative and other concerned parties of the commissioning schedule
866 and of deficiencies and follow-up services undertaken to correct and re-test deficient items for
867 conformance with design intent and prevailing industry Standards.
- 868 • Reviewing and verifying acceptability of Operation and Maintenance (O&M) materials,
869 control sequences and interlocks, contractor startup procedures, and checkout procedures for
870 completeness and accuracy.
- 871 • Providing detailed, data-driven reports of all test records, testing, results, and recommendations.
872 Documenting the dates of acceptance as determined by the general contractor, owner, and
873 design team.

874

875

876 4.4 Electrical Design Engineer Roles and Responsibilities

877

878 The electrical design engineer's responsibilities during the commissioning process typically include, but
879 are not limited to:

- 880 • Developing design intent documentation and establishing the basis of design (BOD) for the
881 project by evaluating the owner's requirements for equipment and systems.
- 882 • Establishing the design criteria, evaluating design concepts, and developing the technical
883 drawings and specifications for the project.
- 884 • Distributing equipment documentation to the CA during the normal submittal process, including
885 detailed startup procedures.
- 886 • Reviewing submittals, shop drawings, and O&M documentation for conformance with project
887 requirements, and recommending their approval or acceptance.
- 888 • Responding to Requests for Information (RFIs).
- 889 • Developing technical requirements for contract modifications or change orders, as needed.
- 890 • Performing periodic construction progress inspections.
- 891 • Ensuring compliance with applicable Codes and Standards.
- 892 • Converting red-lined as-built drawings to a digital format.

893

894

895 4.5 Contractor Roles and Responsibilities

896

897 Contractors typically maintain current marked-up as-built drawings and specifications of all contract
898 documents and contractor-generated coordination and shop drawings during construction, including
899 updating these documents after the completion of commissioning activities and any deferred or seasonal
900 testing. *NOTE: Do not wait to update drawings until the end of construction. Maintain updated*
901 *documents at all times. As-built drawings and data books must be made available for review and use by*
902 *the design engineers (A/E) and other members of the commissioning team approximately two weeks prior*
903 *to the start of commissioning activities*

904

905 Contractors coordinate outside suppliers, equipment manufacturers, test agencies and others as required
906 by the contract documents and the CP. Contractors coordinate work schedules and staffing to ensure that
907 qualified technicians are available and present during the agreed upon schedules and for sufficient
908 duration to complete checks, sequences, procedures, tests, and adjustments, and to resolve deficiencies
909 that are identified in a timely fashion.

910

911 Contractors complete and submit the final as-built documents, drawings and specifications, test reports,
912 completed checklists, and updated shop drawings after commissioning is complete for inclusion in the
913 O&M manuals that are turned over to the owner as part of the required deliverables for final acceptance.

914

915 Each contractor participating in the commissioning process should designate a single-point contact person
916 to work with the owner and other commissioning team members. The contractor's contact person should
917 have the authority to coordinate commissioning activities on behalf of the contractor.

918

919 Contractors typically provide the documentation required for commissioning, such as shop drawings and
920 product submittal data, detailed startup procedures (including manufacturer startup procedures), pre-
921 functional checklists, full sequences of operation, operating and maintenance data, factory performance
922 data, factory prototype test results, functional performance test procedures, control drawings, details of
923 owner-contracted tests, equipment startup certification forms, manufacturer field or factory performance
924 tests, and startup test documentation.

925
926 When factory startup is specified by contract documents, the respective contractor coordinates factory
927 startups with the witnessing parties, such as the CA, owner, A/E and/or other interested commissioning
928 team members. *NOTE: Factory startup activities are generally reviewed and checked prior to functional*
929 *performance tests.*

930
931 Additionally, when testing is completed by one or more independent testing agencies, the respective
932 contractor typically coordinates with each independent testing agency so that the CA, owner, A/E, and/or
933 any interested commission team member can witness such tests to ensure that applicable aspects of the
934 test meet contractual and commissioning requirements, such as requirements of the pre-functional
935 checklists, startups, and/or functional performance tests for the equipment or systems.

936
937 Functional test procedures are reviewed with the A/E, CA, and the respective contractors. Functional
938 testing and procedures are executed by the respective contractors under the direction of and documented
939 by the CA. During initial functional testing and for critical equipment, the A/E may also witness any
940 testing.

941
942 In general, all of the trade contractors participate in the resolution of system deficiencies and any non-
943 compliance in materials, installation, or setup that are identified during the commissioning process in
944 accordance with contract documents and the owner's project requirements.

945
946

947 **4.5.1 General Contractor Roles and Responsibilities**

948

949 During construction, the general contractor's responsibilities include, but are not limited to:

- 950 • Coordinate commissioning activities with the CA.
- 951 • Ensure that commissioning activities are coordinated with the master construction schedule.
- 952 • Ensure that O&M manual content, marked-up as-built copies of drawings and specifications,
953 component submittal drawings, and other pertinent documents are available at the project site
954 during construction for review.
- 955 • Track and maintain all construction documents, addenda, requests for information (RFIs),
956 contract modifications or change orders, and approved submittals and shop drawings related to
957 commissioned equipment and systems.
- 958 • Prepare O&M manuals, according to the contract documents, including clarifying and updating
959 the original sequences of operation to as-built conditions.
- 960 • Provide all requested submittal data, including detailed startup procedures and specific
961 responsibilities of the owner to keep warranties in force.
- 962 • Provide updated, final as-built documents, drawings and specifications, to the CA and A/E for
963 review, approval, and incorporation into record documentation.

964

965 During the warranty period, the general contractor's responsibilities include, but are not limited to:

- 966 • Ensure that subcontractors execute seasonal or deferred functional performance testing, witnessed
967 by the CA, in accordance with the specifications.
- 968 • Ensure that subcontractors correct deficiencies and make necessary adjustments to O&M manuals
969 and as-built drawings for applicable issues identified during any deferred or seasonal testing.

970

971

972 **4.5.2 Mechanical Contractor Roles and Responsibilities**

973

974 Mechanical equipment frequently has electrical and electronic components, such as motors and controls.

975 The mechanical contractor provides and installs mechanical equipment in accordance with the contract
 976 documents, performs pre-functional and functional tests as defined in the CP, and coordinates work with
 977 other trades.

978

979 In general, motors are factory-installed on mechanical equipment or are field-installed on mechanical
 980 equipment by the mechanical contractor. For this reason, the mechanical contractor is typically
 981 responsible for functional testing of motors involving vibration monitoring, balancing, and adjustment.

982

983 In general, the controls contractor is responsible for functional testing of mechanical and environmental
 984 control systems, such as a building automation system (BAS).

985

986

987 **4.5.3 Electrical Contractor Roles and Responsibilities**

988

989 The electrical contractor provides and installs the electrical equipment and furnishes all tools needed to
 990 start up, check out, and conduct functional performance procedures on electrical equipment, components,
 991 and systems.

992

993 The electrical contractor's responsibilities include, but are not limited to:

994

- 995 • Coordinate commissioning activities with the general contractor and the CA.
- 996 • Assist the CA in developing test procedures, checklists, and forms.
- 997 • Execute and document testing according to the specific commissioning requirements of the
 998 project.
- 999 • Monitor the installation of equipment and systems to ensure the equipment, configuration, and
 1000 quality of construction meets the design requirements and approved submittals and shop
 1001 drawings.
- 1002 • Coordinate electrical work related to mechanical systems, including power requirements of
 1003 mechanical equipment, and safeties and interlocks.
- 1004 • Participate in the functional performance procedures as required to achieve design intent.
- 1005 • Schedule manufacturer or factory technicians and representatives, or other specialty trade
 1006 representatives as needed for factory startup and to demonstrate the performance of equipment
 1007 and systems in accordance with contract requirements.
- 1008 • Demonstrate the performance of each piece of equipment to the CA and/or owner.
- 1009 • Participate in off-season mode testing as required to achieve design intent.
- 1010 • Provide O&M data on electrical equipment to the general contractor.
- 1011 • Provide updated as-built documents, drawings and specifications, to the general contractor.
- 1012 • Conduct training on electrical equipment, components, and systems.

1012

1013

1014 **4.6 Documentation**

1015

1016 Contractor commissioning documents which will be completed by the various contractors include, but are
 1017 not limited to, the following:

1018

- 1019 • Weekly commissioning status reports.
- 1020 • Pre-startup contractor test procedures and test forms.
- 1021 • Equipment startup plans and forms.
- 1022 • Post-startup contractor test forms and reports.
- 1023 • Pre-functional tests and checklists.
- Functional performance procedures and tests.

- Operating and maintenance (O&M) manuals.

Commissioning forms, checklists, and related documents are completed concurrently with the commissioning activities being documented. Do not document commissioning activities after-the-fact. Commissioning forms are generally signed by the individuals having responsibility and authority for witnessing completion of the respective inspections and tests.

5. Testing Requirements

In general, procedures and tests are witnessed by the CA, general contractor, and/or owner. Coordinate procedures and tests in advance to ensure that the appropriate personnel will be available to witness procedures and tests. Keep in mind that tests that are not witnessed by the CA or owner may be rejected and may be subject to retesting.

Perform inspections and testing with electrical equipment de-energized when possible. Exercise care when inspecting and testing energized equipment. See Section 3.

Upon completion of all testing, restore all connections, settings, programming, and equipment to normal operating conditions in accordance with contract documents.

Document any deficiencies discovered during testing or other commissioning procedures. See Section 6.2 for additional guidance. Correct deficiencies and retest equipment, sub-systems, or systems to ensure conformance to the design intent.

5.1 Test Equipment

Commissioning electrical equipment may require special tools and instruments for the measurement of the equipment performance. Suitability of test equipment and calibration requirements shall be in accordance with ANSI/NETA ECS Standard for Electrical Commissioning Specifications for Electrical Power Equipment and Systems Sections 5.3 and 5.4. See Annex A for additional requirements for test and measurement equipment, testing procedures, and methodologies.

Commissioning electrical equipment may require special tools and instruments for measurement of the equipment performance. All electrical testing equipment must be of sufficient quality and accuracy to test and/or measure the system performance within tolerance levels specified in the manufacturer specifications and design documents.

Companies providing testing should provide all tools, materials, test instruments, instrumentation, equipment, labor, and technical supervision to perform such tests and inspections. Utilities are typically furnished in accordance with contract documents.

Test equipment shall be calibrated, be in good mechanical and electrical condition, and be used by qualified operators. Field test metering used to check the calibration of power system meters must be more accurate (a minimum of twice the accuracy) than the instrument being tested. The calibrated accuracy of metering in test equipment shall be appropriate for the test being performed. The waveshape and frequency of test equipment output waveforms shall be appropriate for the test and for the equipment being tested.

1074 Method of Procedures (MOPs) that detail the sequence of steps necessary to commission equipment are
1075 typically developed by the organization completing the commissioning procedure. Emergency
1076 procedures must be developed in the event a problem occurs during testing. Include the telephone
1077 numbers of the local electric utility service provider in the MOP.
1078
1079

1080 **5.1.1 Calibration**

1081
1082 Use a regulated, high quality power supply for test equipment during testing, as supply voltage,
1083 frequency, and waveform variation can produce invalid results. Operate all equipment in accordance with
1084 its instruction manual.
1085

1086 All test equipment and instrumentation used for commissioning procedures shall be calibrated according
1087 to the manufacturer-recommended intervals, and after mishandling, or being dropped or damaged. Dated
1088 calibration labels or tags shall be visible on all test equipment, or calibration certificates shall be readily
1089 available. Maintain up-to-date testing and calibration records indicating the dates and results of
1090 instruments calibrated or tested.
1091

1092 Each testing organization shall have a calibration program and documentation that all applicable test
1093 instruments are maintained within the required rated accuracy for each test instrument calibrated. Firms
1094 providing calibration services shall maintain up-to-date instrument calibration instructions and procedures
1095 for each test instrument calibrated. The accuracy of test equipment shall be traceable to the National
1096 Bureau of Standards (NBS) in an unbroken chain.
1097

1098 Ensure that test equipment used for performance verifications during the commissioning process has been
1099 calibrated within one year of its use for testing. Field instruments should be calibrated within 6 months of
1100 use for testing. In the absence of other calibration requirements, test instruments should be calibrated in
1101 accordance with the following maximum frequency schedule:

- 1102 • Field instruments: Analog, 6 months maximum. Digital, 12 months maximum.
- 1103 • Laboratory instruments: 12 months maximum.
- 1104 • Leased specialty equipment: 12 months maximum.

1105

1106

1107 **5.1.2 Data Logging**

1108

1109 Use data logging instruments and software as needed to measure the performance of electrical equipment
1110 and systems over a specified period of time to ensure that equipment and systems are functioning in
1111 accordance with the design intent and specifications. Data logging may require energy management
1112 control system trending, standalone data log monitoring, or manual functional testing.
1113

1114

1115 **5.2 Contractor Pre-Startup, Startup, and Post-Startup Procedures**

1116

1117 *NOTE: General commissioning requirements of electrical equipment, components, conductors,*
1118 *cables, connections, and terminations may be completed at any time prior to acceptance testing or*
1119 *final commissioning procedures. See Section 5.5 for commissioning requirements of electrical*
1120 *equipment that include inspections, checks, and tests that may be completed during pre-startup,*
1121 *startup, and post-startup of equipment, components, and systems.*
1122

1123

1123 The equipment manufacturer standard startup procedures and forms are typically used as the basis of the

1124 commissioning equipment startup procedure and documentation. All startup forms are typically
 1125 submitted to the CA and owner for review and approval prior to equipment startup, and are submitted to
 1126 the CA and owner for review and acceptance upon completion.

1127
 1128 After equipment startup, adjust settings and calibration of equipment in accordance with
 1129 manufacturer instructions, and in accordance with design intent documents, and contract
 1130 documents, drawings and specifications. Provide documentations of the conditions under which
 1131 tests and adjustments were conducted, including (as applicable) ambient conditions, set points,
 1132 override conditions, and status and operating conditions that impact the results of the test.

1133
 1134

1135 **5.3 Pre-Functional Performance Procedures and Checklists**

1136

1137 *NOTE: See Section 5.5 for commissioning requirements of electrical equipment that include*
 1138 *inspections, checks, and tests that may be completed during pre-functional performance procedures*
 1139 *for equipment, components, and systems.*

1140

1141 Pre-functional performance testing is performed to document that the specified equipment, components,
 1142 sub-system, or system is installed correctly, has started up properly, and is ready for functional
 1143 performance testing. Pre-functional performance tests include checking all operating modes, safety
 1144 interlocks, control responses, and specific responses to abnormal or emergency operating conditions.
 1145 Pre-functional performance tests are often documented in a checklist format, and are based on design
 1146 intent documentation and equipment submittals.

1147

1148 Completed checklists and forms are typically submitted to the CA and owner for review upon completion
 1149 of the respective tests. Completed original pre-functional checklists are typically maintained on-site as
 1150 part of the as-built record commissioning documents to be delivered to the owner upon project
 1151 completion.

1152

1153 The CA and/or owner will generally provide oversight to the contractors during the execution of pre-
 1154 functional testing and will periodically review the contractors' in-progress pre-functional checklists for
 1155 accuracy and completeness, and to verify that checklists are being updated.

1156

1157 Pre-functional performance checklists include, at a minimum, that:

- 1158 • Installed equipment matches the specifications and approved submittals and shop drawings.
- 1159 • Equipment is installed in accordance with contract documents, drawings and specifications, and
 1160 manufacturer instructions.
- 1161 • Utility connections to equipment have been successfully completed.
- 1162 • All related equipment has been started up, with start-up reports and pre-functional checklists
 1163 submitted and approved as ready for functional performance testing.
- 1164 • Testing, balancing, and calibration is complete and accepted by the CA.
- 1165 • All control system functions and all interlocking systems are programmed and operable per
 1166 contract documents, including final set points and schedules, with debugging, loop tuning, and
 1167 sensor calibrations completed.
- 1168 • All architectural/engineering (A/E) punch list items for equipment, sub-systems, and
 1169 systems have been corrected.
- 1170 • Functional test procedures have been reviewed and approved by the installing contractor.
- 1171 • Safety, operating ranges, and functions have been reviewed by the CA.
- 1172 • Code-required clearance around equipment is provided for service and maintenance.
- 1173 • A record has been made of all values for pre-test set points that were changed to accommodate

1174 testing. Check boxes can be used to verify that all pre-test set points (control parameters, limits,
 1175 delays, lockouts, and schedules) have been returned to original values.
 1176 • Other operational, safety, alarm checks, and startup reports have been completed successfully.
 1177

1178

1179 **5.4 Functional Performance Procedures**

1180

1181 *NOTE: See Section 5.5 for commissioning requirements of electrical equipment that include*
 1182 *inspections, checks, and tests that may be completed during functional performance procedures for*
 1183 *equipment, components, and systems.*
 1184

1185

1186 In general, specific functional performance procedures and forms are developed by the CA to verify and
 1187 document proper operation of each piece of equipment and each system. Procedures and forms are
 1188 based on the design intent, contract documents, drawings and specifications, contract modifications or
 1189 change orders affecting equipment, and approved submittals and shop drawings,

1190

1191 Complete functional performance procedures on equipment and systems monitored or controlled by a
 1192 control system in conjunction with the controls contractor. Prior to commissioning, verify that the
 1193 controls contractor has completed, debugged, validated, and forwarded all documentation for the control
 1194 system, including point-to-point checks listing command and response values, verification that network
 1195 communication between all devices and systems is established, and the sequence of operation checks out.

1196

1197 Begin functional performance testing after completing pre-functional checklists for systems, sub-
 1198 systems, and equipment, and checklists have been approved, and after all issues and deficiencies
 1199 affecting equipment and system operation or performance have been resolved.

1200

1201 Each functional performance test should be performed under conditions that simulate actual operating
 1202 conditions as closely as possible. Optimally, each system and sub-system should be operated through all
 1203 modes of operation, such as seasonal, occupied, unoccupied, warm-up, cool-down, partial load, and full-
 1204 load, where there is a specified system response.

1205

1206 Verify the proper sequence of operation for equipment, and verify the settings of adjustable parameters
 1207 for equipment and systems. Test each step in every written sequence and other significant modes,
 1208 sequences, and operational features not mentioned in written sequences; including startup, normal
 1209 operation, shutdown, scheduled on and off, unoccupied and manual modes, safeties, alarms, over-rides,
 1210 lockouts, and power failures.

1211

1212 Verify shut down and restart capabilities both for scheduled and unscheduled events, such as power
 1213 failure recovery and normal scheduled start/stop functions. When applicable, demonstrate a full cycle
 1214 from off to on and no load to full load and then to no load and off. Verify time of day schedules and
 1215 setpoints. Verify all energy saving control strategies.

1216

1217 Conduct seasonal functional performance testing on equipment during the season it is intended to operate,
 1218 such as testing air conditioning equipment during the peak cooling season, and testing heating equipment
 1219 during the peak heating season. Verify energy efficiency and self-diagnostic capability of equipment and
 1220 systems.

1221

1222 Verify the proper operation of equipment and systems in normal and alternate modes of operation, and
 1223 during abnormal operation conditions, such as (where applicable) fire, single-phasing, total power
 failure, equipment failure, and individual component failure. Verify the proper operation of safeties and

1224 interlocks. Verify proper operation of control systems, including response times, stability, and tunings.
1225
1226 Simulate conditions by imposing an artificial load when it is not practical to test design conditions under
1227 actual operating conditions, and only upon the approval of the CA and owner. Before simulating
1228 conditions, calibrate test instruments. Set and document simulated conditions and methods of simulation.
1229 When simulating conditions is not practical, alter set points to conduct functional testing only upon
1230 approval of the CA and owner.

1231
1232 Upon satisfactory completion of all verified tests, return equipment and system settings to normal
1233 operating conditions as required by the contract documents as a complete and operational system.
1234

1235

1236 **5.5 Commissioning Requirements of Electrical Equipment**

1237

1238 [For additional information, refer to ANSI/NETA Standard for Acceptance Testing Specifications](#)
1239 [\(ATS\) and ANSI/NETA Standard for Electrical Commissioning \(ECS\).](#)
1240

1241

1242

1242 **5.5.1 General Electrical Commissioning Requirements**

1243

1244 Perform specific inspections and mechanical tests of equipment and components in accordance with the
1245 manufacturer instructions [and ANSI/NETA ATS and ECS specifications.](#)
1246

1247

1248 Compare equipment, components, conductors, cables, connections, and terminations with contract
1249 documents, drawings and specifications, and with approved submittals, product data and shop drawings.
1249 Verify equipment nameplate information with contract documents, drawings and specifications, approved
1250 submittals, and short circuit and coordination studies, if applicable. Verify circuit breaker and fuse sizes,
1251 types, and ratings conform to contract documents and approved submittals. Measure the resistance of
1252 fuses. Resistance values must not deviate by more than 15 percent between identical fuses.
1253

1254

1255 Perform point-to-point wiring checks to ensure that each conductor is properly terminated. Verify that
1256 temporary wiring jumpers are removed. Check the continuity of each conductor from end-to-end,
1257 including ground conductors and ground shields of shielded cables and conductors. Perform a shield-
1258 continuity test on each shielded cable using a low-resistance ohmmeter. [Shields must be disconnected](#)
1259 [from any bonding point and individually tested.](#) Shielding must exhibit continuity [less than 10 ohm](#)
[resistance.](#) Investigate any shield resistance values that exceed ten ohms per 1000 feet of cable.
1260

1261

1262 Inspect the condition of exposed cable and conductor insulation, jacketing, and field-applied
1263 fireproofing, where installed. Verify that visible cable bends are not less than the ICEA and/or
1264 manufacturer minimum allowable bending radius. Check that conductors and cables are supported
independently of terminations and connections.
1265

1266

1267 Verify correct connections in accordance with single-line and three-line diagrams. Perform a phasing
1268 check on equipment supplied from multiple sources, such as double-ended switchgear, to insure correct
bus phasing from each source.
1269

1270

1271 Verify proper mechanical, maintenance, and ventilation clearances for equipment. Verify that field
1272 wiring is clear of energized bus. Verify that conductors and cables are secured in accordance with
1273 manufacturer instructions to withstand the effects of fault currents. Verify proper separation and
clearances of conductors and cables, including primary and secondary conductors for transformers.

- 1274
- 1275 Verify the identification and correct arrangement of cables, conductors, connections, and terminations.
- 1276 Check that each conductor, each connection, and each termination is properly identified (cable number,
- 1277 wire number) and color coded in accordance with contract requirements and in accordance with the NEC.
- 1278 Verify identification of all lighting circuits and branch circuits on panel directories.
- 1279
- 1280 Perform a visual and mechanical inspection of equipment, components, conductors, cables, connections,
- 1281 and terminations. Verify that equipment is completely assembled. Verify that equipment and components
- 1282 are clean, dry, and free of tools, debris, and storage of materials. Verify that shipping braces, blocking,
- 1283 brackets, and similar supports have been removed from equipment. Inspect all bus bracing and insulators
- 1284 for contamination, tracking, and broken or missing parts.
- 1285
- 1286 Check for physical damage. Inspect doors, panels, and sections of equipment for damage to paint, dents,
- 1287 and scratches, paying particular attention to missing and loose parts and hardware, bent hinges, broken or
- 1288 missing lock handles or latches, and warped panels. Check for proper clearances, anchorage, fit, and
- 1289 alignment, considering seismic requirements. Check for proper alignment and fit of doors, access panels,
- 1290 and components. Check the interior of equipment for missing or loose parts and hardware. Verify that
- 1291 connections and terminations are free of corrosion.
- 1292
- 1293 Using a calibrated torque wrench, verify the tightness of accessible bolted electrical connections in
- 1294 accordance with manufacturer published data. Torque all connections in accordance with the
- 1295 manufacturer recommendations and record the results on a tabular form. Alternatively, inspect bolted
- 1296 electrical connections for high resistance using a low-resistance ohmmeter. See Annex A for additional
- 1297 guidance.
- 1298
- 1299 Inspect compression-applied connectors and terminations for correct cable match and indentation.
- 1300 Inspect conductor and cable shield grounding, cable support, and termination. If cables are
- 1301 terminated through window-type current transformers, inspect to verify that neutral and ground
- 1302 conductors are correctly placed and that shields are correctly terminated for proper operation of
- 1303 protective devices.
- 1304
- 1305 Verify proper grounding in accordance with contract documents, drawings and specifications, and in
- 1306 accordance with the NEC. Ensure that equipment grounding conductors, grounding electrode conductors,
- 1307 and bonding jumpers are properly sized, properly installed, and properly torqued.
- 1308
- 1309 Verify that all grounding and shorting contacts for instrument transformers (potential transformers and
- 1310 current transformers) provide proper contact. Verify proper operation of disconnecting and grounding
- 1311 devices associated with drawout devices, such as circuit breakers, control power transformers, and
- 1312 potential transformers, including control contacts, grounding contacts, and withdrawal mechanisms, if
- 1313 applicable.
- 1314
- 1315 Test all safety devices, fail-safe functions, and all keyed, mechanical, and electrical safety and interlock
- 1316 systems for correct operation and sequencing. Attempt to close locked open devices. Attempt to open
- 1317 locked closed devices. Exchange keys and attempt operation with devices operated in off-normal
- 1318 positions.
- 1319
- 1320 Verify that settings for alarm, control, and trip setpoints for adjustable trip circuit breakers, relays, meters,
- 1321 and temperature indicators are adjusted in accordance with contract documents, drawings and
- 1322 specifications, approved submittals, product data and shop drawings, manufacturer instructions, and
- 1323 approved short circuit and coordination studies. Verify that circuit breaker addresses for microprocessor-

- 1324 communication packages correspond to contract documents and approved submittals.
1325
1326 Verify the correct level of liquid in liquid-filled devices, such as liquid-filled transformers and bushings,
1327 and wet-cell batteries. Check for leaks. Verify the presence of PCB content labeling for liquid-filled
1328 equipment, such as transformers, reactors, and capacitors. Verify that positive pressure is maintained on
1329 gas-blanketed transformers.
1330
1331 Manually operate disconnecting means, circuit breakers and switches, to verify proper alignment and
1332 smooth operation. Electrically exercise all electrically-operated devices such as circuit breakers, under
1333 no-load condition to verify proper operation. Leave disconnecting means, circuit breakers and switches,
1334 in the OPEN position after inspecting and operating and before initial energization.
1335
1336 Verify the correct operation of all sensing devices, alarms, and indicating devices.
1337
1338 Perform insulation resistance testing of conductors and busing. See Annex A for additional information.
1339
1340 Perform infrared scan (thermographic survey) of equipment and components under maximum load
1341 conditions. See Annex A for additional information.
1342
1343 Check for unusual sounds after energizing equipment, components, conductors, and systems.
1344
1345

1346 **5.5.2 Medium and High Voltage Power Cables (above 600V)**

1347

- 1348 Perform acceptance testing on cables, including terminations and joints (tees, taps, and splices), after
1349 completing the cable system installation and before the cable system is energized and placed into service,
1350 in accordance with ANSI/IEEE 400, ICEA S-93-639/NEMA WC 74, ICEA S-94-649 and ICEA S-97-
1351 682.
1352
1353 Ensure that cables are disconnected from equipment and de-energized. *NOTE: Lower test voltages are*
1354 *required when cables remain connected to equipment and accessories.* Ensure that the maximum test
1355 voltage does not exceed the limits for terminations specified in ANSI/IEEE 48, IEEE 386, or
1356 manufacturer specifications. Disconnect and ground surge arresters, potential transformers, and
1357 capacitors. Ensure that conductors under test are properly isolated from ground and are guarded against
1358 inadvertent contact by personnel. Tie back cables as needed to ensure adequate clearance from any
1359 grounded objects.
1360
1361 Test each conductor individually. Test each cable section separately. Do not separate permanent joints to
1362 test sections of cable. Ground all conductors, shields, and drain wires not under test. Prepare and clean
1363 exposed ends of cable prior to testing in order to minimize any leakage current using manufacturer
1364 approved materials, such as denatured alcohol or approved equivalent. Perform testing after terminations
1365 and splices using hot dielectric compounds have fully cooled to ambient temperature.
1366
1367 Acceptance testing can be performed by means of direct voltage (DC), alternating voltage (AC), partial
1368 discharge (PD), or very low frequency (VLF) AC in accordance with Annex A. Evaluate alternative
1369 methods in selecting the appropriate acceptance test for each given cable installation. Do not exceed 80
1370 percent of the cable manufacturer factory test value or the maximum test voltage in Annex A, whichever
1371 is less. Keep in mind that the maximum test voltage may be limited by cable terminations or joints that
1372 may have lower maximum voltage ratings than the maximum recommended acceptance test voltages for
1373 the cable alone.

1374
1375 Perform high-potential testing only on new conductors. Do not perform high-potential testing on
1376 conductors that have been in service for more than five (5) years, including testing new conductors
1377 spliced or tapped onto existing conductors. Complete high-potential testing on sections of new cable
1378 prior to connecting new cable to existing cable. DC high-potential, very low frequency (VLF) AC
1379 testing, or any other type of withstand or destructive testing is not recommended as a maintenance test on
1380 any medium-voltage cable, especially XLPE cable that has been in service in a wet environment for more
1381 than five years, unless approved by the cable manufacturer.

1382
1383 Acceptance testing must be performed on new cable prior to connecting to existing cables. After
1384 acceptance testing is completed for the new cable, join the new cable to the existing cable and perform
1385 insulation-resistance and shield-continuity testing on the length of new and existing cable including any
1386 joints.

1387
1388 Current-sensing circuits in test equipment, when used, must measure only the leakage current associated
1389 with the cable under test and must not include internal leakage of the test equipment. Terminations must
1390 be adequately corona-suppressed by guard ring, field reduction sphere, or other suitable method, as
1391 necessary. If acceptance testing is performed by means of direct voltage (DC), reduce the test set
1392 potential to zero and measure residual voltage at discrete intervals. Apply grounds for a time period
1393 adequate to drain all insulation-stored charge.

1394
1395 After energizing cables, check for unusual sounds that might indicate partial discharge (corona) or loose
1396 connections. Perform infrared scan in accordance with Annex A.

1397
1398 See NECA 600 for additional guidance.

1399
1400

1401 **5.5.3 Low Voltage Power Cable (below 600V)**

1402
1403 Perform insulation resistance testing in accordance with Annex A.

1404
1405

1406 **5.5.4 Electrical Feeders and Branch Circuits (600V or below)**

1407
1408 Make operational checks on all lighting circuits and branch circuits to demonstrate that all circuits
1409 perform all functions for which they were designed. In the presence of the CA, field test for correct
1410 labeling of circuits and equipment by breaking current and observing loss of power at circuits or
1411 equipment. Document, correct, and retest any incorrect equipment circuit identifications found.

1412
1413

1414 **5.5.5 Liquid-Filled Transformers**

1415
1416 Verify that transformer bushings are clean.

1417
1418 Verify correct primary and secondary fuse sizing for voltage transformers with fusing as overcurrent
1419 protection.

1420
1421 Verify correct liquid level in all tanks and bushings.

1422
1423 Where installed, verify that alarm, control and trip settings on temperature and level indicators, pressure

- 1424 relief device, and fault pressure relay are as specified.
- 1425
- 1426 Where installed, verify that cooling fans and pumps operate correctly and that fan and pump motors have
- 1427 correct overcurrent protection.
- 1428
- 1429 Perform a turns-ratio test on all no-load tap-changer positions and all load tap-changer positions. Verify
- 1430 that the final tap setting is as specified. Verify that winding polarities are in accordance with nameplate
- 1431 data. Turns-ratio test results should not deviate more than one-half percent from either the adjacent coils
- 1432 or the calculated nameplate ratio.
- 1433
- 1434 Measure resistance of each high-voltage winding in each no-load tap-changer position. Measure
- 1435 resistance of each low-voltage winding in each load tap-changer position, if applicable. Consult the
- 1436 manufacturer if winding-resistance measurements vary more than one percent from adjacent windings.
- 1437
- 1438 Perform a core resistance test. If the transformer core ground strap is removable, remove the core ground
- 1439 strap and measure the insulation resistance of the transformer core at 500 volts DC. Core insulation-
- 1440 resistance values should be comparable to factory test results, but not less than 2.0 megohm at 500 volts
- 1441 DC.
- 1442
- 1443 Perform excitation-current tests in accordance with test equipment manufacturer published data. Typical
- 1444 excitation-current test data pattern for a three-legged core transformer is two similar current readings and
- 1445 one lower current reading.
- 1446
- 1447 Where installed, test transformer neutral grounding impedance device. Compare grounding impedance
- 1448 device results to manufacturer published data
- 1449
- 1450 Perform an insulation resistance test and calculate dielectric absorption or polarization index in
- 1451 accordance with Annex A. Perform testing for each winding-to-winding and on each winding-to-ground.
- 1452
- 1453 Perform a power factor test on transformer bushings that are equipped with power factor taps, and
- 1454 perform hot collar watts-loss test on filled bushings that are not equipped with power factor taps, in
- 1455 accordance with Annex A.
- 1456
- 1457 Remove a sample of insulating liquid in accordance with ASTM D 3613 and perform dissolved-gas
- 1458 analysis (DGA) in accordance with ANSI/IEEE C57.104 or ASTM D3612. Evaluate results of dissolved-
- 1459 gas analysis in accordance with ANSI/IEEE C57.104. Use results as baseline for future tests.
- 1460
- 1461 Remove a sample of insulating liquid in accordance with ASTM D-923 and test for the following:
- 1462
- 1463 • Dielectric breakdown voltage in accordance with ASTM D-877 and/or ASTM D-1816.
 - 1464 • Acid neutralization number in accordance with ASTM D-974.
 - 1465 • Specific gravity in accordance with ASTM D-1298.
 - 1466 • Interfacial tension in accordance with ASTM D-971 or ASTM D-2285.
 - 1467 • Color in accordance with ASTM D-1500.
 - 1468 • Visual Condition in accordance with ASTM D-1524.
 - 1469 • Parts per million of water in accordance with ASTM D-1533. (Required for all liquid-filled
 - 1470 transformer rated 25 kV or higher, and for all silicone-filled transformers.)
 - 1471 • Measure dissipation factor or power factor in accordance with ASTM D-924.
- 1472 Insulating liquid must comply with manufacturer instructions.
- 1473 Investigate the presence of oxygen in the nitrogen gas blanket, if applicable.

1474
1475 See NECA 410 for additional guidance.

1476
1477

1478 **5.5.6 Dry-Type Transformers**

1479
1480 Verify correct primary and secondary fuse sizing for voltage transformers.

1481
1482 Verify that resilient mounts are free.

1483
1484 Where installed, verify that auxiliary devices, such as cooling fans and controls, alarms, indicators, and
1485 tap changers, operate correctly. Test temperature control panel and verify alarm settings on temperature
1486 indicators, and test interlocks for shutdown. Adjust settings in accordance with the manufacturer
1487 instructions as needed. Verify that cooling fan motors have correct overcurrent protection.

1488
1489 Perform a turns-ratio test on all no-load tap-changer positions and all load tap-changer positions. Verify
1490 that the final tap setting is as specified. Verify that winding polarities are in accordance with nameplate
1491 data. Turns-ratio test results should not deviate more than one-half percent from either the adjacent coils
1492 or the calculated nameplate ratio.

1493
1494 Perform an insulation resistance test and calculate dielectric absorption or polarization index in
1495 accordance with Annex A. Perform testing for each winding-to-winding and on each winding-to-ground.

1496
1497 Measure excitation-current on each phase. Typical excitation current results for a typical three-legged
1498 core transformer are the two outer legs have similar current readings, and the center leg has a lower
1499 current reading.

1500
1501 Measure the resistance of each winding at each tap connection. Temperature corrected winding-
1502 resistance test results should compare within one percent of previously obtained results.

1503
1504 Perform core resistance test. If the transformer core is insulated and the core ground strap is removable,
1505 remove the core ground strap and measure the insulation resistance of the transformer core at 500 volts
1506 DC. Core insulation-resistance values should be comparable to factory test results, but not less than 1.0
1507 megohm at 500 volts DC.

1508
1509 Verify correct secondary voltage phase to phase and phase to neutral after energization and prior to
1510 loading.

1511
1512 See NECA 409 for additional guidance.

1513
1514

1515 **5.5.7 Instrument Transformers**

1516
1517 Verify correct primary and secondary fuse sizing for voltage transformers.

1518
1519 Perform insulation resistance testing in accordance with Annex A. Perform measurements from winding
1520 to winding and from winding to ground.

1521
1522 Measure the transformer turns ratio. Confirm transformer polarity by electrical testing.

1523

1524 Verify CT secondary connections by driving a low current through the secondary leads and checking for
1525 this current at applicable devices.

1526
1527 Verify potential transformer (PT) secondary connections by applying a low voltage to the secondary leads
1528 and checking for this voltage at applicable devices. Verify correct secondary voltage by energizing
1529 primary winding with system voltage. Measure secondary voltage with the secondary wiring
1530 disconnected. Verify correct potential at all devices.

1531
1532 Perform a secondary saturation test of current transformers (CTs) at a minimum of three points below and
1533 one point above the knee of the saturation curve.

1534
1535 Measure voltage circuit burdens at transformer terminals. Perform burden tests at the secondary leads of
1536 each CT to assure accurate translation of primary current.

1537
1538 Check the PT secondary load with secondary voltage and current measurements. Transformer loading
1539 must be less than the volt-ampere capacity of the PT.

1540
1541 Verify that current circuits are grounded and have only one grounding point in accordance with
1542 ANSI/IEEE C57.13.3.

1543
1544 Measure the capacitance of coupling-capacitor voltage transformer capacitor sections. Capacitance of
1545 capacitor sections of coupling-capacitance voltage transformers must be in accordance with the
1546 manufacturer published data.

1547
1548 Perform secondary wiring integrity test. Disconnect the transformer at the secondary terminals and
1549 connect the secondary wiring to a rated secondary voltage source. Verify correct potential at each device.

1550

1551

1552 **5.5.8 Switchgear and Switchboard Assemblies Rated 1200A or Greater**

1553

1554 Perform an insulation resistance test on each bus section, phase-to-phase and phase-to-ground, and on all
1555 control wiring in accordance with Annex A. *NOTE: When performing dielectric tests, disconnect all*
1556 *instrument and control transformers, lightning arresters, surge protective devices (SPDs), digital meters*
1557 *and relays, and other sensitive electronic equipment that may cause erroneous results or cause damage to*
1558 *equipment that is not rated in accordance with switchgear or switchboard industry Standards. Minimum*
1559 *test voltages and insulation resistances are shown in Table 1.*

1560

Table 1 Minimum Test Voltage and Insulation Resistance		
Voltage Rating	Minimum Test Voltage	Minimum Insulation Resistance
0-250V	500V DC	25 <u>Megohms</u>
250-600V	1000V DC	100 <u>Megohms</u>
601-5000V	2500V DC	DC 1000 <u>Megohms</u>

5001-15,000V	2500V DC	DC 5000 <u>Megohms</u>
--------------	----------	-----------------------------------

1561
1562
1563
1564

Perform a power factor test. For switchgear rated 5 kV and above, power factor should not exceed the values shown in Table 2.

Table 2 Switchgear Power Factor Values		
Power Factor Values		
Voltage Rating (volts)	Test Voltage (volts)	Maximum Reading
5000	5000	2%
7000	5000	2%
15,000	10,000	2%
35,000	10,000	2%

1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596

For medium-voltage switchgear, after achieving acceptable insulation resistance test results, perform high-potential testing on each bus section, each phase to ground with phases not under test grounded in accordance with the manufacturer published data (see Annex A for additional guidance). Perform high-potential testing on each bus section, each phase to ground with phases not under test grounded, in accordance with manufacturer published data. Apply test voltage for one minute.

Perform current tests by primary or secondary injection on all metering and relaying circuits in each section of switchgear with a sufficient current magnitude to cause a minimum of 1.0 ampere current flow in the secondary circuit. Verify correct magnitude of current at each device in the circuit.

Verify that the insulating barriers and shutters are properly installed and operating correctly. Inspect all mechanical indicating devices for correct operation. Check indicating lights for proper operation. Replaced burned-out lamps. Verify that filters are in place and/or vents are clear. Verify proper operation of switchgear/switchboard heaters.

Perform a phasing check on switchgear with multiple sources to insure correct bus phasing from each source. Verify the proper operation of control transfer relays located in switchgear with multiple control power sources.

After energization, verify proper voltage with system operating at load conditions. Operate every circuit breaker, switch, and contactor, manually and electrically, if so equipped. Modify tap settings on transformers as needed for actual operating conditions. Measure line amperes with the system operating under load conditions.

Perform infrared scan in accordance with Annex A. Identify all hot spots, and promptly correct sources of heating problems.

See NECA 400 and NECA 430 for additional guidance.

5.5.9 Metal-Enclosed (Medium-Voltage) Bus and Low-Voltage Busway

- 1597
1598 Confirm the physical orientation of the busway is in accordance with manufacturer labels to insure
1599 adequate cooling. Examine outdoor busway to ensure the removal of weep-hole plugs, if applicable,
1600 and the correct installation of joint shields.
1601
1602 Measure insulation resistance of each bus, phase-to-phase and each phase-to-ground, for a minimum of
1603 one (1) minute in accordance with Annex A, with phases not under test grounded.
1604
1605 Perform high-potential testing of each phase-to-ground with phases not under test grounded, in
1606 accordance with manufacturer published data and in accordance with Annex A. Apply test voltage for
1607 one minute. Busway insulation should withstand the overpotential test voltage applied.
1608
1609 Perform contact-resistance test on each connection point of uninsulated busway. On insulated
1610 busway, measure resistance of assembled busway sections and compare values with adjacent
1611 phases. See Annex A for additional guidance.
1612
1613 Perform phasing test on each busway tie section energized by separate sources to insure correct bus
1614 phasing from each source. Test with busway energized from permanent sources.
1615
1616 Verify proper operation of busway space heaters.
1617
1618 After energizing busway, perform infrared scan of all accessible bus joints and cable connections while
1619 maintaining maximum load on the bus for at least one hour, or until the temperature has stabilized, to
1620 detect loose or high resistance connections and other circuit anomalies. See Annex A for additional
1621 guidance.
1622
1623 See NECA 408 for additional guidance.
1624
1625
1626 **5.5.10 Motor Control Centers**
1627
1628 Measure insulation resistance of the line bus, phase-to-phase and phase-to-ground. See Annex A
1629 for additional guidance.
1630
1631 Perform operational tests on each starter. Test overload relays by primary current injection and monitor
1632 the trip time of each overload relay. Compare against manufacturer published data and either replace or
1633 resize relays that are deficient. Measure insulation resistance of motor starters, phase-to-phase and phase-
1634 to-ground, with the starter contact closed and overload relays in the “open” position. See Annex A for
1635 additional guidance.
1636
1637 After energizing, perform infrared scan in accordance with Annex A. Identify all hot spots and correct
1638 sources of heating problems promptly.
1639
1640 See NECA 402 for additional guidance.
1641
1642
1643 **5.5.11 Low-Voltage Motor Starters**
1644
1645 Verify contactor mechanical operation. Inspect that contact gap, wipe, alignment, and pressure are in
1646 accordance with manufacturer published data.

1647
1648 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with the starter
1649 closed and across each open pole for one minute. Test voltage must be in accordance with manufacturer
1650 published data. See Annex A for additional guidance.

1651
1652 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
1653 components, follow manufacturer recommendations. See Annex A for additional information.

1654
1655 Test motor protection devices in accordance with manufacturer published data. Verify that the overload
1656 element rating is correct for its application. If motor-running protection is provided by fuses, verify
1657 correct fuse ratings. Set adjustable or programmable devices according to the protective device
1658 coordination study.

1659

1660

1661 **5.5.12 Medium-Voltage Motor Starters**

1662

1663 Verify racking mechanism operation for removable units.

1664

1665 Verify contactor mechanical operation. Inspect that contact gap, wipe, alignment, and pressure are in
1666 accordance with manufacturer published data.

1667

1668 Measure the resistance of power fuses. Resistance values must not deviate by more than 15 percent
1669 between identical fuses. Measure blowout coil circuit resistance. Test starting transformers, if applicable.
1670 Test starting reactors, if applicable. Verify proper operation of cubicle space heaters, if applicable.

1671

1672 Exercise all active components and confirm correct operation of all indicating devices. Verify correct
1673 barrier and shutter installation and operation.

1674

1675 Perform insulation-resistance tests on contactors, phase-to-phase and phase-to-ground, and across open
1676 contacts for one minute. Test voltage must be in accordance with manufacturer published data. See
1677 Annex A for additional guidance.

1678

1679 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
1680 components, follow manufacturer recommendations. See Annex A for additional information.

1681

1682 Test motor protection devices in accordance with manufacturer published data. Verify that the overload
1683 element rating is correct for its application. If motor-running protection is provided by fuses, verify
1684 correct fuse ratings. Set adjustable or programmable devices according to the protective device
1685 coordination study.

1686

1687 Perform vacuum bottle integrity (high-potential) testing across each vacuum bottle with the contacts in
1688 the open position in strict accordance with manufacturer published data. Do not exceed the maximum
1689 voltage recommended by the manufacturer for this test. *NOTE: Some DC high-potential test sets are*
1690 *half wave rectified and may produce peak voltages in excess of the vacuum bottle manufacturer*
1691 *recommended maximum.* See Annex A for additional guidance. Provide adequate barriers and protection
1692 against X-radiation during this test. Do not perform this test unless the contact displacement of each
1693 interrupter is within manufacturer tolerance. The interrupter must withstand the overpotential test voltage
1694 applied.

1695

1696 Energize each contactor using an auxiliary source. Adjust armature to minimize operating vibration

1697 where applicable.

1698

1699

1700 **5.5.13 Medium-Voltage Circuit Breakers**

1701

1702 Verify racking mechanism operation for removable breakers.

1703

1704 Perform circuit breaker time-travel analysis to determine the opening and closing speeds of each breaker,
1705 the interval for closing and tripping, and the contact bounce.

1706

1707 Perform a contact resistance test of each phase and compare results. See Annex A for additional
1708 guidance.

1709

1710 Perform an insulation resistance test. Measure insulation resistance phase-to-phase and phase-to-ground
1711 and across open poles, using a minimum voltage of 2500V DC. See Annex A for additional guidance.

1712

1713 Perform a power factor/dissipation test with the breaker in the open and closed positions. See
1714 Annex A for additional guidance.

1715

1716 Perform high-potential testing in accordance with manufacturer published data. See Annex A for
1717 additional guidance.

1718

1719 See NECA 430 for additional guidance.

1720

1721

1722 **5.5.14 Medium-Voltage Air Circuit Breakers**

1723

1724 Perform all mechanical operation tests on the operating mechanism in accordance with manufacturer
1725 instructions. Inspect moving and stationary contacts for condition and alignment. Verify that the arc
1726 chutes are intact. Inspect puffer operation. Verify cell fit and element alignment. Verify racking
1727 mechanism operation for removable breakers.

1728

1729 Perform time-travel analysis. Circuit breaker operation times must conform to manufacturer published
1730 data. If recommended by the manufacturer, slow close/open the breaker and check for binding, friction,
1731 contact alignment, and penetration. Verify that the contact sequence is in accordance with manufacturer
1732 published data. In the absence of manufacturer published data, refer to ANSI/IEEE C37.04.

1733

1734 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with circuit breaker
1735 closed and across each open pole for one minute. Test voltage must be in accordance with manufacturer
1736 published data. See Annex A for additional guidance.

1737

1738 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
1739 components, follow manufacturer recommendations. See Annex A for additional information.

1740

1741 Perform a contact/pole-resistance test. Measure blowout coil circuit resistance.

1742

1743 Perform minimum pickup voltage tests on trip and close coils. Minimum pickup for trip and close coils
1744 must be in accordance with manufacturer published data.

1745

1746 With breaker in the test position, trip and close the breaker with the control switch. Trip each breaker by

1747 operating each of its protective relays. Verify trip-free and anti-pump functions.

1748

1749 Perform power-factor or dissipation-factor test with breaker in both the open and closed positions.

1750 Compare power-factor or dissipation-factor test results with previous tests of similar breakers or
1751 manufacturer published data.

1752

1753 Perform high-potential testing in accordance with manufacturer published data. The insulation must
1754 withstand the overpotential test voltage applied.

1755

1756

1757 **5.5.15 Medium-Voltage Vacuum Circuit Breakers**

1758

1759 Perform all mechanical operation tests on both the circuit breaker and its operating mechanism. Verify
1760 racking mechanism operation for removable breakers.

1761

1762 Measure critical distances such as contact gap, as recommended by manufacturer. Contact displacement
1763 must be in accordance with factory recorded data marked on the nameplate of each vacuum breaker or
1764 bottle.

1765

1766 Perform time-travel analysis. Compare travel and velocity values to manufacturer published data.

1767

1768 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with circuit breaker
1769 closed and across each open pole for one minute. Test voltage must be in accordance with manufacturer
1770 published data. See Annex A for additional guidance.

1771

1772 Perform power-factor or dissipation-factor tests on each pole with the breaker open and each phase with
1773 the breaker closed. Compare power-factor or dissipation-factor test results to manufacturer published
1774 data. In the absence of manufacturer published data, compare results to similar breakers.

1775

1776 Perform power-factor or dissipation-factor tests on each bushing. Use hot collar procedures if bushings
1777 are not equipped with a power-factor tap. Power-factor or dissipation-factor test results and capacitance
1778 test results should be within ten percent of nameplate rating for bushings.

1779

1780 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
1781 components, follow manufacturer recommendations. See Annex A for additional information.

1782

1783 Perform a contact/pole-resistance test. Verify trip, close, trip-free, and anti-pump functions. Trip each
1784 circuit breaker by operation of each protective device.

1785

1786 Perform minimum pickup voltage tests on trip and close coils. Minimum pickup for trip and close coils
1787 must be in accordance with manufacturer published data.

1788

1789 Perform vacuum bottle integrity (high-potential) testing across each vacuum bottle with the breaker in the
1790 open position in strict accordance with manufacturer published data. Do not exceed the maximum
1791 voltage recommended by the manufacturer for this test. *NOTE: Some DC high-potential test sets are*
1792 *half wave rectified and may produce peak voltages in excess of the vacuum bottle manufacturer*
1793 *recommended maximum.* See Annex A for additional guidance. Provide adequate barriers and protection
1794 against X-radiation during this test. Do not perform this test unless the contact displacement of each
1795 interrupter is within manufacturer tolerance. The interrupter must withstand the overpotential test voltage
1796 applied.

1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846

5.5.16 Medium-Voltage SF₆ (Sulfur Hexafluoride) Circuit Breakers

Verify racking mechanism operation for removable breakers.

Inspect operating mechanism and SF₆ gas-insulated system in accordance with the manufacturer published data.

Verify correct operation of alarms and pressure-limit switches for pneumatic, hydraulic, and SF₆ gas pressure as recommended by the manufacturer. Test for SF₆ gas leaks if temperature-corrected pressure/density alarms or meters indicate a need. Remove a sample of SF₆ gas (if provisions are made for sampling) and test.

If recommended by the manufacturer, slow close/open the breaker and check for binding, friction, contact alignment, and penetration. Verify that the contact sequence is in accordance with manufacturer published data. In the absence of manufacturer published data, refer to ANSI/IEEE C37.04.

Perform time-travel analysis. Compare travel and velocity values to manufacturer published data.

Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with the circuit breaker closed and across each open pole for one minute. For single-tank breakers, perform insulation resistance tests from pole-to-pole. Test voltage must be in accordance with manufacturer published data. See Annex A for additional guidance.

Perform power-factor or dissipation-factor tests on each pole with the breaker open and each phase with the breaker closed. Compare power-factor or dissipation-factor test results to manufacturer published data. In the absence of manufacturer published data, compare results to similar breakers.

Perform power-factor or dissipation-factor tests on each bushing. Use hot collar procedures if bushings are not equipped with a power-factor tap. Power-factor or dissipation-factor test results and capacitance test results should be within ten percent of nameplate rating for bushings.

Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state components, follow manufacturer recommendations. See Annex A for additional information.

Perform a contact/pole-resistance test. Verify trip, close, trip-free, and anti-pump functions. Trip each circuit breaker by operation of each protective device.

Perform minimum pickup voltage tests on trip and close coils. Minimum pickup for trip and close coils must be in accordance with manufacturer published data.

Perform high-potential testing in accordance with manufacturer published data. Perform SF₆ bottle integrity test (high-potential) across each SF₆ bottle with the contacts in the open position in strict accordance with manufacturer published data. Do not exceed the maximum voltage recommended by the manufacturer for this test. See Annex A for additional guidance. The insulation must withstand the overpotential test voltage applied.

Perform magnetron atmospheric condition (MAC) test on each vacuum interrupter. In the absence of manufacturer's published data, each vacuum interrupter pressure shall not be greater than 1×10^{-2} Pa and

1847 shall not deviate from adjacent poles by more than two orders of magnitude.
1848
1849

1850 **5.5.17 Low-Voltage Air-Insulated and Insulated Case Circuit Breakers**

1851
1852 Perform all mechanical operation tests on circuit breakers and the operating mechanism in accordance
1853 with the manufacturer published data. Check adjustments on springs, gears, and liners. Check cell fit and
1854 element alignment. Inspect arc chutes.
1855

1856 Perform a contact resistance or millivolt drop test on each phase and compare results. See Annex
1857 A for additional guidance.
1858

1859 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with the circuit
1860 breaker closed and across each open pole for a minimum of one minute. Test voltage must be in
1861 accordance with the manufacturer published data. See Annex A for additional guidance.
1862

1863 Perform a primary current injection test to determine minimum pickup current and long-time delay (at
1864 300% pickup current), short-time pickup and time delay, instantaneous pickup current, and ground-fault
1865 pick up and time delay. *NOTE: Remove or otherwise bypass current-limiting fuses from circuit breakers*
1866 *so equipped prior to applying simulated overload and fault current.* Compare results with the time-
1867 current coordination curve for each circuit breaker. Verify trip unit characteristics. Set adjustable or
1868 programmable devices according to the protective device coordination study. Replace defective devices,
1869 and adjust and retest where necessary.
1870

1871 Verify proper operation of auxiliary functions, such as shunt trip, undervoltage relays, and ground-fault, if
1872 applicable, in accordance with manufacturer instructions.
1873

1874

1875 **5.5.18 Low-Voltage (600V Class) Network Protectors**

1876
1877 Verify trip-free operation. Verify correct operation of the auto-open-close control handle. Verify that the
1878 protector closes automatically with the source voltage available on the transformer side only. Verify that
1879 the protector opens automatically when the source feeder breaker is opened.
1880

1881 Verify that arc chutes are intact. Inspect moving and stationary contacts for condition and alignment.
1882 Verify that primary and secondary contact wipe and other dimensions (vital to the satisfactory operation
1883 of the breaker) are correct. Perform mechanical operator and contact alignment tests on both the breaker
1884 and its operating mechanism.
1885

1886 Verify cell fit and element alignment. Verify proper racking mechanism operation. Verify appropriate
1887 lubrication on moving current-carrying parts. Verify appropriate lubrication on moving and sliding
1888 surfaces. Perform a leak test on submersible enclosure in accordance with manufacturer published data.
1889

1890 Verify that maintenance devices are available for servicing and operating the breaker.
1891

1892 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with the protector
1893 closed and across each open pole for a minimum of one minute. Test voltage must be in accordance with
1894 manufacturer published data. See Annex A for additional guidance.
1895

1896 Verify current transformer ratios.

- 1897
1898 Perform a contact/pole-resistance test. Measure the resistance of each power fuse for protectors so
1899 equipped.
1900
1901 Measure the minimum pickup voltage of the motor control relay. Verify that the motor can charge the
1902 closing mechanism at the minimum voltage specified by the manufacturer. Minimum acceptable motor
1903 closing voltage must not exceed 75 percent of the rated control circuit voltage.
1904
1905 Measure minimum pickup voltage of the trip actuator. Minimum voltage to operate the trip actuator must
1906 not exceed 7.5 percent of rated control circuit voltage. Verify that the actuator resets correctly.
1907
1908 Calibrate the network protector relays in accordance with manufacturer instructions. Adjust relay settings
1909 in accordance with the short circuit and coordination study.
1910
1911 Verify phase rotation, phasing, and synchronized operation as required by the application.
1912
1913

1914 **5.5.19 Low Voltage Air Switches**

- 1915
1916 Verify correct blade alignment, blade penetration, travel stops, and mechanical operation. Verify
1917 appropriate lubrication on moving current-carrying parts. Verify appropriate lubrication on moving and
1918 sliding surfaces.
1919
1920 Measure contact-resistance across each switchblade and fuseholder. Measure fuse resistance. Investigate
1921 fuse-resistance values that deviate from each other by more than 15 percent. Verify that each fuse has
1922 adequate mechanical support and contact integrity. Check that fuse clips are tight, secure, and free of
1923 corrosion. Verify correct phase barrier installation.
1924
1925 Verify correct operation of all indicating and control devices. Test ground-fault protection systems in
1926 accordance with Section 5.5.25.
1927
1928 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with the switch
1929 closed and across each open pole for a minimum of one minute. Test voltage must be in accordance with
1930 manufacturer published data. See Annex A for additional guidance.
1931
1932 Verify cubicle space heater operation, if so equipped.
1933
1934

1935 **5.5.20 High and Medium-Voltage Air Switches**

- 1936
1937 Verify correct blade alignment, blade penetration, travel stops, and mechanical operation. Verify that
1938 expulsion-limiting devices are in place on all holders having expulsion-type elements. Verify that each
1939 fuseholder has adequate mechanical support and contact integrity. Check that fuse clips are tight, secure,
1940 and free of corrosion.
1941
1942 Measure contact-resistance across each switchblade and fuseholder. Measure fuse resistance. Investigate
1943 fuse-resistance values that deviate from each other by more than 15 percent. Verify that each fuse has
1944 adequate mechanical support and contact integrity. Check that fuse clips are tight, secure, and free of
1945 corrosion. Verify correct phase barrier installation.
1946

1947 Verify correct operation of all indicating and control devices. Verify appropriate lubrication on moving
 1948 current-carrying parts. Verify appropriate lubrication on moving and sliding surfaces.

1949
 1950 Perform insulation-resistance tests on each pole, phase-to-phase and phase-to-ground, with the switch
 1951 closed and across each open pole for a minimum of one minute. Test voltage must be in accordance with
 1952 manufacturer published data. See Annex A for additional guidance.

1953
 1954 After achieving acceptable insulation resistance test results, perform high-potential testing on each pole
 1955 with the switch closed. Test each pole-to-ground with all other poles not under test grounded in
 1956 accordance with the manufacturer published data (see Annex A for additional guidance). Apply test
 1957 voltage for one minute. The insulation must withstand the overpotential test voltage applied.

1958
 1959 Verify cubicle space heater operation.

1960
 1961

1962 **5.5.21 Protective Relays and Metering Devices**

1963

1964 Inspect meters, relays, and cases for physical damage, especially where subject to movement or the
 1965 possibility of pinched wires in doors or access panels, broken parts, and indication of shipping damage.
 1966 Remove shipping restraint material from protective relays, meters, and cases, if applicable.

1967
 1968 Clean relays. If the relay design permits, remove each relay from its case to inspect and clean. Inspect
 1969 for loose screws, friction in moving parts, iron filings between the induction disk and permanent magnet,
 1970 if applicable, and any evidence of damage with the relay.

1971
 1972 Verify meter connections in accordance with single line meter and relay diagrams. Tighten case
 1973 connections. Verify that mounting hardware and connections are tight. Inspect covers for correct gasket
 1974 seal. Clean cover glass. Inspect shorting hardware, case-shortening contacts, connection paddles, and/or
 1975 knife switches. Verify the target reset.

1976
 1977 Inspect meters and relays for foreign material, particularly in disk slots of damping and electromagnets.
 1978 Remove any foreign material from the case.

1979
 1980 Verify disk clearances. Verify contact clearance and spring bias. Inspect spiral spring convolutions.
 1981 Inspect disks and contacts for freedom of movement, end play, alignment of rotating disk(s) and correct
 1982 travel. Burnish contacts as needed in accordance with manufacturer instructions. Inspect bearings and/or
 1983 pivots.

1984
 1985 Determine the accuracy of all meters and verify watthour meter operation. Verify the accuracy of meters
 1986 at all cardinal points. Calibrate watthour meters according to manufacturer published data. Calibrate all
 1987 meters at mid scale. *NOTE: Calibration instrument precision should be 50-percent or less than the*
 1988 *precision of the instrument being tested. For example, if the instrument being tested has a precision of*
 1989 *plus or minus 10-percent, the precision of the calibration instrument should be plus or minus 5-percent or*
 1990 *better.* Calibrate watt-hour meters to 0.50-percent. Verify instrument multipliers.

1991
 1992 Set relays and confirm proper fuse sizes and types in accordance with the engineer's specified values
 1993 indicated in the coordination study report and related material. Test meters and protective relays at the
 1994 specified settings.

1995
 1996 Perform insulation resistance tests in accordance with relay or metering component and test instrument

1997 manufacturer instructions. Disconnect and isolate conductors, components, and equipment normally
 1998 connected to equipment under test, including phase and neutral connections, surge protective devices,
 1999 meters, relays, and control power and instrument transformers. Ground conductors, components, and
 2000 equipment not being tested. Perform insulation resistance tests on protective and control relays, from
 2001 circuit-to-frame. Follow manufacturer instructions for allowable testing procedures for solid-state and
 2002 microprocessor-based relays.

2003

2004 *NOTE: Do not perform insulation resistance testing or over-potential (high-potential) testing of solid-*
 2005 *state electronic devices, relays, or meters. Perform diagnostic tests on electronic, solid-state components*
 2006 *in accordance with manufacturer instructions.*

2007

2008 Inspect targets and indicators. Determine pickup and dropout of electromechanical targets. Verify
 2009 correct operation of all light-emitting diode indicators. Set the contrast for liquid-crystal display readouts
 2010 for readability.

2011

2012 Set relays per engineer's specified values, electrically test, and verify functional operation of relays:

2013

- Timing Relay (ANSI Device Number 2 or 62): Determine the time delay. Verify proper operation of instantaneous contacts.

2014

- Distance Relay (ANSI Device Number 21): Determine the maximum reach. Determine the maximum torque angle. Determine the offset.

2015

- Volts Per Hertz Relay (ANSI Device Number 24): Determine the pickup frequency at rated voltage. Determine the pickup frequency at a second voltage level. Determine the time delay.

2016

- Synchronism-Check Relay (ANSI Device Number 25): Determine the closing zone at rated voltage. Determine the maximum voltage differential that permits closing at zero degrees.

2017

- Determine the live line, live bus, dead line, and dead bus set points. Determine the time delay. Verify the dead bus/live line, dead line/live bus, and dead bus/dead line control functions.

2018

- Undervoltage Relay (ANSI Device Number 27): Determine the dropout voltage. Determine the time delay. Determine the time delay at a second point on the timing curve for inverse time relays.

2019

- Directional Power Relay (ANSI Device Number 32): Determine the minimum pickup at maximum torque angle. Determine the closing zone. Determine the maximum torque angle. Determine the time delay. Verify the time delay at a second point on the timing curve for inverse time relays. Perform phase angle and magnitude contribution tests, to vectorially prove polarity and connection of differential and directional relays.

2020

- Loss of Excitation Relay (ANSI Device Number 40): Determine the maximum reach. Determine the maximum torque. Determine the offset.

2021

- Reverse Phase or Phase Current Balance Relay (ANSI Device Number 46): Determine the pickup of each unit. Determine the percent slope. Determine the time delay.

2022

- Negative Sequence Current Relay (ANSI Device Number 46N): Determine the negative sequence alarm level. Determine the negative sequence minimum trip level. Determine the maximum time delay. Verify two points on the time-current characteristic curve.

2023

- Phase Sequence Voltage Relay (ANSI Device Number 47): Determine the positive sequence voltage to close the normally open contact. Determine the positive sequence voltage to open the normally closed contact (undervoltage trip). Verify the negative sequence trip. Determine the time delay to close the normally open contact with sudden application of 120 percent of pickup. Determine the time delay to close the normally closed contact upon removal of voltage when previously set to rated system voltage.

2024

- Machine or Transformer Replica-type Thermal Relay (ANSI Device Number 49R): Determine the time delay at 300 percent of setting. Determine a second point on the operating curve.

2025

Determine the pickup.

2046

- 2047 • Machine or Transformer Temperature Relay (ANSI Device Number 49T): Determine the trip
2048 resistance. Determine the reset resistance.
- 2049 • Instantaneous Overcurrent Relay (ANSI Device Number 50): Determine the pickup. Determine
2050 the dropout. Determine the time delay.
- 2051 • AC Time Overcurrent Relay (ANSI Device Number 51): Determine the minimum pickup.
2052 Determine the time delays at two points on the time current curve.
- 2053 • Power Factor Relay (ANSI Device Number 55): Determine the tripping angle. Determine the
2054 time delay.
- 2055 • Overvoltage Relay (ANSI Device Number 59): Determine the overvoltage pickup. Determine
2056 the time delay to close the contact with sudden application of 120% of pickup.
- 2057 • Voltage Balance Relay (ANSI Device Number 60): Determine the voltage difference to close the
2058 contacts with one source at rated voltage.
- 2059 • Transformer Sudden Pressure Relay (ANSI Device 63): Determine the rate-of-rise or the pickup
2060 level of suddenly applied pressure in accordance with manufacturer specifications. Verify the
2061 operation of the 63 FPX seal-in circuit. Verify the trip circuit to a remote breaker.
- 2062 • Ground-Protective Relay (ANSI Device Number 64): Determine the maximum impedance to
2063 ground causing relay pickup.
- 2064 • AC Directional Overcurrent Relay (ANSI Device Number 67): Determine the directional unit
2065 minimum pickup at maximum torque angle. Determine the closing zone. Determine the
2066 overcurrent unit pickup. Determine the overcurrent unit time delay at two points on the time-
2067 current curve. Perform phase angle and magnitude contribution tests, to vectorially prove
2068 polarity and connection of differential and directional relays.
- 2069 • AC Reclosing Relay (ANSI Device Number 79): Determine the time delay for each programmed
2070 reclosing interval. Verify lockout for unsuccessful reclosing. Determine the reset time. Verify
2071 the instantaneous overcurrent lockout.
- 2072 • Frequency Relay (ANSI Device Number 81): Verify the frequency set points. Determine the
2073 time delay. Determine the undervoltage cutoff.
- 2074 • Carrier or Pilot-Wire Receiver Relay (ANSI Device Number 85): Determine the overcurrent
2075 pickup. Determine the undercurrent pickup. Determine the pilot wire ground pickup level.
- 2076 • Differential Relay (ANSI Device Number 87): Determine the operating unit pickup. Determine
2077 the operation of each restraint unit. Determine the slope. Determine the harmonic restraint.
2078 Determine the instantaneous pickup. Perform phase angle and magnitude contribution tests, to
2079 vectorially prove polarity and connection of differential and directional relays.
- 2080 • Multi-function solid-state relays: Perform manufacturer recommended tests and self-testing of
2081 relays. Document functional settings of relays using printouts or by scrolling through relay
2082 settings. Record model number, style number, serial number, firmware revision, software
2083 revision, and rated control voltage. Download all events from the event recorder in filtered and
2084 unfiltered mode before performing any tests on the relay. Download the sequence-of-events
2085 recorder prior to testing the relay. Verify the operation of light-emitting diodes, display, and
2086 targets. Record the passwords for all access levels. Clean the front panel and remove foreign
2087 material from the case. Check that connections are tight. Verify that the frame is grounded in
2088 accordance with manufacturer instructions. Download settings from the relay. Print a copy of
2089 the settings for the commissioning report and compare the settings to those specified in the
2090 coordination study. Apply voltage or current to all analog inputs and verify correct registration of
2091 the relay meter functions. Check the functional operation of each element used in the protection
2092 scheme as described for electromechanical and solid-state relays in accordance with each relay
2093 function. Check the operation of all active digital inputs. Check all output contacts or SCRs,
2094 preferably by operating the controlled device such as circuit breaker, auxiliary relay, or alarm.
2095 For pilot schemes, perform a loop-back test to check the receive and transmit communication
2096 circuits. For pilot schemes with direct transfer trip (DTT), perform transmit and received DTT at

2097 each terminal. Upon completion of testing, reset all min/max recorders, fault counters, sequence
2098 of events recorder, and all event records. Verify all inputs, outputs, internal logic, and timing
2099 elements used in protection, metering, and control functions.

2100
2101 Verify that each set of relay contacts perform its intended function in the control scheme including
2102 breaker trip tests, close inhibit tests, 86 lockout tests, and alarm function.

2103
2104 After the equipment is initially energized, measure the magnitude and phase angle of all inputs and
2105 compare to expected values.

2106
2107 Use the manufacturer recommended tolerances when other tolerances are not specified. When critical test
2108 points are specified in contract documents or engineering reports, calibrate the relay to those points even
2109 though other test points may be out of tolerance.

2110
2111 See NECA 430 for additional guidance.

2112
2113

2114 **5.5.22 Molded-Case Circuit Breakers**

2115
2116 Operate each circuit breaker to insure smooth operation. Inspect the case, operating mechanism, contacts,
2117 and arc chutes for cracks and other defects. Verify proper operation of the circuit breaker charging
2118 mechanism, if so equipped. Check trip unit reset operation.

2119
2120 Perform a contact resistance test of each phase and compare results. See Annex A for additional
2121 guidance.

2122
2123 Perform an insulation resistance test from each pole-to-pole and each pole-to-ground with the breaker
2124 closed and across open contacts of each phase using a test voltage in accordance with manufacturer
2125 instructions for a minimum of one minute. See Annex A for additional guidance.

2126
2127 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
2128 components, follow manufacturer recommendations. See Annex A for additional information.

2129
2130 Check circuit breakers for proper mounting, conductor size (ampacity), and feeder designation. Check
2131 the tightness of connections with a calibrated torque tool, such as a torque screwdriver or torque wrench,
2132 in accordance with manufacturer instructions.

2133
2134 Perform a primary current injection test to determine minimum pickup current and long-time delay (at
2135 300% pickup current), short-time pickup and time delay, instantaneous pickup current, and ground-fault
2136 pick up and time delay. Determine the instantaneous pickup current by run-up or pulse method. Clearing
2137 times should be within six (6) cycles or less. Record trip times. Compare results with the time-current
2138 coordination curve for each circuit breaker. Verify trip unit characteristics. Set adjustable or
2139 programmable devices according to the protective device coordination study. Replace defective devices,
2140 adjust, and retest where necessary. *NOTE: Remove or otherwise bypass current-limiting fuses from
2141 circuit breakers so equipped prior to applying simulated overload and fault current. NOTE: All tripping
2142 times should fall within the manufacturer time current coordination tolerance band. Circuit breakers
2143 with trip times varying from published tolerance band more than 10% at three hundred percent (300%)
2144 current should be replaced.*

2145
2146 Perform minimum operation voltage tests on shunt trip and close coils in accordance with manufacturer

2147 instructions.

2148

2149 Activate auxiliary protective devices, such as ground fault or under voltage relays, to verify the operation
2150 of shunt trip devices. Test ground-fault to ensure activation based on time current coordination curve for
2151 the ground fault relay.

2152

2153 Verify correct operation of any auxiliary features such as trip and pickup indicators, zone interlocking,
2154 electrical close and trip operation, trip-free, and anti-pump functions.

2155

2156 Test AFCI and GFCI circuit breakers in accordance with manufacturer instructions. Turn off and unplug
2157 all appliances from receptacles supplied by AFCI and GFCI circuit breakers prior to testing. Test circuit
2158 breakers by pressing the TEST button. Circuit breakers should trip when the TEST button is pressed, and
2159 the handle should move to the center or TRIPPED position. Reset circuit breakers by moving the handle
2160 fully to the OFF position, then fully to the ON position. If the circuit breaker opens when the TEST
2161 button is pressed and can be reset, the circuit breaker is functioning properly. If the circuit breaker does
2162 not open when the test button is pressed or cannot be reset, the circuit breaker is defective and must be
2163 replaced. *NOTE: OSHA does not recognize the use of hand held AFCI test indicators, and circuit
2164 breaker manufacturers only recognize the use of the test button on the circuit breaker as the proper test
2165 method for AFCI circuit breakers.*

2166

2167 See NECA 407 for additional guidance. Also, see NECA 169 for additional information for GFCI/AFCI
2168 circuit breakers.

2169

2170

2171 **5.5.23 Low-Voltage Power Circuit Breakers**

2172

2173 Perform all mechanical operator and contact alignment tests on both the breaker and its operating
2174 mechanism in accordance with manufacturer published data.

2175

2176 Verify that arc chutes are intact. Inspect moving and stationary contacts for condition, wear, and
2177 alignment. Verify that primary and secondary contact wipe and other dimensions vital to the satisfactory
2178 operation of the breaker are correct. Verify cell fit and element alignment. Verify racking mechanism
2179 operation. Verify appropriate lubrication on moving current-carrying parts. Verify appropriate
2180 lubrication on moving and sliding surfaces.

2181

2182 Perform an insulation resistance test from each pole-to-pole and each pole-to-ground with the breaker
2183 closed and across open contacts of each phase using a test voltage in accordance with manufacturer
2184 instructions for a minimum of one minute. See Annex A for additional guidance.

2185

2186 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
2187 components, follow manufacturer recommendations. See Annex A for additional information.

2188

2189 Perform a contact resistance test of each phase and compare results. See Annex A for additional
2190 guidance.

2191

2192 Perform a primary current injection test to determine the minimum pickup current and long-time delay (at
2193 300% pickup current), short-time pickup and time delay, instantaneous pickup current, and ground-fault
2194 pick up and time delay. Determine the instantaneous pickup current by run-up or pulse method. Clearing
2195 times should be within six (6) cycles or less. Record trip times. Compare results with the time-current
2196 coordination curve for each circuit breaker. Verify trip unit characteristics. Set adjustable or

2197 programmable devices according to the protective device coordination study. Replace defective devices,
 2198 adjust, and retest where necessary. *NOTE: Remove or otherwise bypass current-limiting fuses from*
 2199 *circuit breakers so equipped prior to applying simulated overload and fault current. NOTE: All tripping*
 2200 *times should fall within the manufacturer time current coordination tolerance band. Circuit breakers*
 2201 *with trip times varying from published tolerance band by more than 10% at three hundred percent*
 2202 *(300%) current should be replaced.*

2203
 2204 Perform minimum operation voltage tests on shunt trip and close coils in accordance with manufacturer
 2205 instructions.

2206
 2207 Verify proper operation of any auxiliary features such as trip and pickup indicators, zone interlocking,
 2208 electrical close and trip operation, trip-free, anti-pump function, trip unit battery condition, and reset all
 2209 trip logs and indicators.

2210
 2211 Verify proper operation of the circuit breaker charging mechanism.

2212
 2213

2214 **5.5.24 Grounding Systems**

2215
 2216 Visually examine grounding conductors and paths, such as raceway couplings, fittings, and connectors.
 2217 Check the tightness of conductor and raceway connections.

2218
 2219 Confirm that the neutral is grounded only at the service equipment. Confirm that the neutral is not
 2220 grounded on the load side of the service disconnecting means enclosure. *NOTE: It is important to*
 2221 *coordinate this testing and follow proper test procedures when performing insulation resistance testing*
 2222 *on conductors and equipment.*

2223
 2224 Inspect ground conductors, ground buses, and connections for conformance with design specifications
 2225 and NEC requirements. Verify that the grounding system is in compliance with drawings, specifications,
 2226 and NEC.

2227
 2228 Perform three-point fall-of-potential tests in accordance with IEEE 81, Section 9.04, on the main
 2229 grounding electrode system. Test each ground rod individually, and test all ground rods interconnected as
 2230 a system. Resistance values must be no greater than those specified in the contract documents. *NOTE:*
 2231 *In general, the maximum resistance to ground should be ~~less~~ greater than 5 ohms. In general, if a single*
 2232 *electrode has a resistance of 25 ohms or less, a supplemental electrode shall not be required.*

2233
 2234 Ground resistance testing should be conducted only when the earth is dry, and a minimum of 48 hours
 2235 after the most recent precipitation. Record the ambient temperature, date, time, approximate water table
 2236 level (as obtained from local geologists), type of earth materials, and measured earth resistivity.

2237
 2238 Perform the two-point method test in accordance with IEEE 81 to determine the ground resistance
 2239 between the main grounding system and all major electrical equipment frames, system neutral, and/or
 2240 derived neutral points. Resistance values must be no greater than those specified in the contract
 2241 documents. *NOTE: In general, the maximum resistance to ground should be ~~less~~ more than 5 ohms. In*
 2242 *general, if a single electrode has a resistance of 25 ohms or less, a supplemental electrode shall not be*
 2243 *required.* Alternatively, perform ground continuity test between main grounding system and equipment
 2244 frame, system neutral and/or derived neutral point by passing a minimum of 10 amperes DC current
 2245 between the ground reference system and the ground point to be tested. Measure voltage drop and
 2246 calculate resistance by the voltage drop method. Investigate point-to-point resistance values which

2247 exceed 0.5 ohm.

2248

2249 Verify the equipment grounding path to earth, including ground rods and interconnecting wiring, ground
2250 buses on equipment, room and pullbox connections, and associated intermediate copper ground
2251 conductors, and structural steel or reinforcing bar connections, rod connection and intermediate conductor
2252 in tests, where applicable.

2253

2254 Notify the CA immediately in writing if the specified ground resistance cannot be obtained with the
2255 grounding system installed in accordance with the construction documents and in accordance with the
2256 NEC.

2257

2258 After energizing, measure phase-to-phase, phase-to-neutral, and neutral-to-ground voltages to confirm
2259 proper neutral-to-ground bonding.

2260

2261

2262 **5.5.25 Ground-Fault Protection Systems**

2263

2264 Test ground-fault protection systems installed on services when first installed on site. Conduct testing in
2265 accordance with manufacturer instructions. Maintain a written record of testing, and make available to
2266 the Authority Having Jurisdiction when requested. For Healthcare Facilities and Critical Operations
2267 Power Systems, test each level of ground-fault protection. Ensure that all levels of ground-fault
2268 protection achieve 100 percent selectivity. See NECA 700 for additional guidance.

2269

2270 Inspect ground-fault protection system components for damage and errors in polarity or conductor
2271 routing. Inspect the neutral main bonding connection. Verify that the ground connection is made
2272 upstream of the neutral disconnect link and on the line side of any ground fault sensor. Verify that neutral
2273 sensors are connected with correct polarity on both the primary and secondary. Verify that all phase
2274 conductors and the neutral pass through the sensor in the same direction for zero sequence systems.
2275 Verify that grounding conductors do not pass through zero sequence sensors. Verify that the grounded
2276 conductor is solidly grounded. Verify correct operation of all functions of the self-test panel. Verify trip
2277 operation, no trip test, and non-automatic reset.

2278

2279 For summation type systems utilizing phase and neutral current transformers, verify correct polarities by
2280 applying current to each phase-neutral current transformer pair. This test also applies to molded-case
2281 breakers utilizing an external neutral current transformer. The relay should operate when the current
2282 direction is the same relative to polarity marks in the two current transformers. The relay should not
2283 operate when the current direction is opposite relative to polarity marks in the two current transformers.

2284

2285 Disconnect the neutral link and perform neutral insulation resistance testing. See Annex A for additional
2286 guidance. Record the insulation resistance, and replace the neutral link. *NOTE: Insulation resistance*
2287 *test results should indicate that no shunt ground paths exist.*

2288

2289 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
2290 components, follow manufacturer recommendations. See Annex A for additional information.

2291

2292 Determine the relay pickup current by primary current injection at the sensor and the circuit interrupting
2293 device operated. The relay pickup current must be within ten percent (10%) of the device dial or fixed
2294 setting, and in no case greater than twelve hundred (1200) amperes. Verify that the relay does not operate
2295 at 90 percent of the pickup setting. Verify that the pickup is less than 125 percent of setting or 1200
2296 amperes, whichever is less.

2297
2298 Test the relay timing by injecting one hundred fifty percent (150%) and three hundred percent (300%) of
2299 the pickup current into the sensor. Electrically monitor and record total trip time. Relay timing must be
2300 in accordance with manufacturer published time current characteristics curves but in no case longer than
2301 one second at 3000 amperes.

2302
2303 Test system operation at fifty-seven percent (57%) of rated voltage.

2304
2305 Test the zone interlock system by simultaneous sensor current injection and monitor the zone blocking
2306 function.

2307
2308 Inspect zero sequence systems for symmetrical alignment of core balance transformers about all current
2309 carrying conductors.

2310
2311 Set pick up and time delay settings in accordance with the short circuit and coordination study.

2312
2313 See NECA 400 for additional guidance.

2314
2315

2316 **5.5.26 Panelboards**

2317
2318 Check all panelboards for proper load balance between phase conductors and adjust the loads as
2319 necessary to bring unbalanced phases within 20% of average load. Measure and record current readings
2320 on all phase conductors and the neutral conductor. Ensure that the circuit directory for each panel is
2321 updated after load balancing, typed, and placed in each panel.

2322
2323 Check torque and tighten all accessible connections to manufacturer specifications.

2324
2325 Perform infrared scan in accordance with Annex A. Perform infrared scan after each panel has been
2326 operating with maximum load for at least one hour or until the temperature has stabilized. Identify all
2327 hot spots, and promptly correct sources of heating problems. Verify the panelboard does not have a
2328 neutral to ground bond unless at the service entrance.

2329
2330 See NECA 407 for additional guidance.

2331
2332

2333 **5.5.27 Receptacles and Wiring Devices**

2334
2335 Test every installed receptacle and wiring device for proper phasing and grounding. Test for open
2336 ground, reversed polarity, open hot, open neutral, hot and ground reversed, and neutral and hot open.
2337 Verify the continuity of the grounding circuit in each receptacle and wiring device.

2338
2339 Test the retention force of the grounding blade of each receptacle (except pin-and-sleeve and locking-type
2340 receptacles). Replace devices with less than 115 g (4 ounces) of retention force.

2341
2342 Test each GFCI receptacle and each GFCI circuit breaker to ensure that the ground-fault circuit
2343 interrupter will not operate when subjected to a ground-fault current of less than 4 milliamperes, and
2344 will operate when subjected to a ground-fault current exceeding 6 milliamperes. Perform testing with an
2345 instrument specifically designed and manufactured for testing ground-fault circuit interrupters. *NOTE:*
2346 *Pushing the receptacle or circuit breaker "TEST" button operation is not acceptable as a substitute for*

2347 *this test.* Replace GFCI receptacles or circuit breakers that do not shut off power at 5 milliamperes
2348 within 1/40th of a second.

2349
2350 Test AFCI receptacles using the test button on the receptacle in accordance with the manufacturer
2351 instructions. *NOTE: OSHA does not recognize the use of hand-held test indicators, and receptacle*
2352 *manufacturers only recognize the use of the test button on receptacles as the proper test method for AFCI*
2353 *receptacles.*

2354
2355 Replace defective AFCI and GFCI devices and retest. If the new receptacle provides the same result,
2356 troubleshoot devices, fixed wiring, and appliances connected to the circuit. Correct any deficiencies and
2357 retest.

2358
2359 After energizing receptacles and wiring devices and placing under normal loads, check for evidence of
2360 thermal damage. Where there is evidence of overheating or failure, perform appropriate thermal
2361 evaluation and other tests to determine the extent of damage. Make repairs, rework wiring, and replace
2362 damaged devices as needed.

2363
2364 Test receptacle circuits for voltage drop, impedance on phase and neutral conductors, and proper
2365 GFCI/AFCI operation at the last receptacle on the branch line. *NOTE: Circuits used for computers or*
2366 *voltage sensitive equipment, at design amperage, should not be less than 6% and for all other circuits less*
2367 *than 10% of design. At all times the voltage at the receptacle should not drop below 111 volts.*

2368
2369 Demonstrate the operation of each switch, timer, and other electrical control wiring device with the
2370 systems fully energized and operating. Demonstrate each operation a minimum of three times.

2371
2372 Replace receptacles and devices that are deficient, and retest.

2373
2374 See NECA 130 and NECA 169 for additional guidance.

2375
2376

2377 **5.5.28 Engine Generators**

2378
2379 Verify that the generator is mounted in such a manner to prevent combustible materials from
2380 accumulating under the generator. Inspect for and remove any foreign objects or loose debris, such as
2381 remaining packing materials, building materials, tools, hardware, rags, paper, and leaves, that could be
2382 drawn into the generator or alternator air intakes. Ensure that the generator and the surrounding area are
2383 clean, dry, and free from obstructions. Ensure that all covers and guards are in place and secure.

2384
2385 Perform a phase rotation test. Verify that the alternator is connected for the required voltage and phase
2386 rotation. Measure the clearance in the generator and exciter air gap. Verify that the air gap is in
2387 accordance with manufacturer specifications. Check the alternator for loose items such as shaft keys, and
2388 couplings. Tighten or replace loose or damaged components.

2389
2390 Inspect the insulation on all conductors. Replace conductors with damaged insulation. Inspect
2391 connections and terminations for damage. Repair or replace damaged connections and terminations.
2392 Support all conductors to prevent stress on connections and termination, and to protect conductors from
2393 damage from rotating parts and sharp edges.

2394
2395 Check bolts, fasteners, and hardware for tightness. Torque hardware in accordance with manufacturer
2396 instructions.

- 2397
- 2398 Measure the winding resistance using a DC bridge and a meter capable of readings in the milli-ohm
- 2399 range. Correct measured values to operating temperature and calculate copper (I^2R) losses and efficiency,
- 2400 and compare with manufacturer specifications.
- 2401
- 2402 Perform insulation resistance and dielectric tests. Calculate polarization index and dielectric absorption,
- 2403 and perform insulation power factor testing in accordance with IEEE Standard 43. See Annex A for
- 2404 additional guidance. Perform tests on armature and rotating or stationary field windings.
- 2405
- 2406 Perform high-potential testing on alternators with ratings greater than 600 Volts. See Annex A for
- 2407 additional guidance. Test each phase separately with the other phases and the winding temperature
- 2408 detectors grounded. Disconnect any capacitors and surge arrestors during the test.
- 2409
- 2410 Perform a vibration test for each main bearing cap. Vibration levels must be in accordance with
- 2411 manufacturer published data.
- 2412
- 2413 Verify proper operation of the engine governor and alternator voltage regulator systems upon initial start-
- 2414 up in accordance with manufacturer instructions. Verify proper frequency and voltage magnitude at no-
- 2415 load with the engine operating at rated speed.
- 2416
- 2417 Verify all generator functions. Functionally test engine shutdown for low oil pressure, over-temperature,
- 2418 over-speed, and other protection features as applicable. Verify all alarms, meters, and auxiliaries and
- 2419 interlocks to the building automation system (BAS). Verify fuel system, fuel storage tank, and level and
- 2420 low fuel indication alarms.
- 2421
- 2422 Verify appropriate mechanical system and control system restart functions of all equipment served by the
- 2423 generator. Verify combustion and ventilation air damper functions and pressure drop of exhaust for
- 2424 generators located indoors.
- 2425
- 2426 Verify proper operation of multiple generators operating in parallel, including operating sequence, lead-
- 2427 lag generator controls, governors, regulators, speed control, and load sharing, including sharing real
- 2428 power and reactive power (cross-current compensation or VAR control). Verify that load-sharing
- 2429 controls are set in accordance with manufacturer instructions. Functionally test the system by removing
- 2430 one generator from the system and verifying that the remaining generator(s) operate automatically and
- 2431 properly. Verify soft-loading capability of each generator for systems with a closed-transition between
- 2432 sources.
- 2433
- 2434 Perform load bank testing of each generator in accordance with contract documents. In the absence of
- 2435 contractual requirements, perform the following load test. Apply step (block) loads of 0 percent, 25
- 2436 percent, 50 percent and 100 percent of full load nameplate rating in 15-minute intervals. Record voltage,
- 2437 current, frequency, and all gaged engine conditions at each step. Operate the generator at 100 percent of
- 2438 full load nameplate real power rating for a minimum of four hours. Record voltage, current, frequency,
- 2439 and all gaged engine conditions every 15 minutes during the full-load test. Verify all generator-running
- 2440 characteristics. Verify starting battery-charging system.
- 2441
- 2442 Perform functional testing of generator systems, including automatic transfer switches (ATSs) and
- 2443 uninterruptible power supplies (UPSs). Include power outage simulations, start-up and transfer of power
- 2444 to the generator system, operation of loads connected to the generator system, start-up and shut-down of
- 2445 equipment related to the fire alarm system, electrical power distribution systems, motor control centers
- 2446 and starters, and variable frequency drives, as applicable. Load bank test the UPS if necessary for the
- 2447 UPS to supply load during testing. Using a power line disturbance monitor, measure and record time

2448 delays for each power failure to each engine start command, engine start command to engine start
2449 (cranking time), engine start to the point where the generator is operating at rated voltage and frequency
2450 and total time from power failure until the loads are connected to the generator system.

2451
2452 Verify that each piece of generator control equipment, such as ATSS, can independently start the
2453 generator system and transfer its load to generator power.

2454
2455 Verify that adjustable settings are set in accordance with manufacturer instructions and recommendations.

2456
2457 See NECA/EGSA 404 and NECA 406 for additional guidance.

2458
2459

2460 **5.5.29 Automatic Transfer Switches (ATSS)**

2461
2462 Commission each ATSS separately to verify that each ATSS starts the generator system and transfers its
2463 load to generator power independently of all other ATSSs.

2464
2465 Check transfer switches for completeness of assembly. Check switches for proper alignment, and for
2466 loose parts and insulation damage. Verify proper grounding.

2467
2468 Verify that manual transfer warnings are attached and visible. Perform manual transfer operation. Verify
2469 positive mechanical interlocking between normal and alternate sources.

2470
2471 Perform an insulation resistance test on each pole from phase-to-phase and phase-to-ground with the
2472 switch closed and across each open pole in accordance with manufacturer instructions for a minimum of
2473 one minute. Perform test with the switch in both the normal and emergency source positions. See Annex
2474 A for additional guidance.

2475
2476 Perform insulation-resistance tests on all control wiring with respect to ground. For units with solid-state
2477 components, follow manufacturer recommendations. Verify the tightness of all control connections. See
2478 Annex A for additional information.

2479
2480 Perform a contact resistance test of each phase and compare results. See Annex A for additional
2481 guidance.

2482
2483 Monitor and document ATSS settings and timers for manual testing/transfer, normal voltage sensing
2484 relays, emergency voltage sensing relays, in-phase monitor, time delay upon transfer, alternate voltage
2485 sensing relay, interlocks and limit switch functions, and timing delay and retransfer upon normal power
2486 restoration over the course of testing transfer switches. Adjust timer settings in accordance with
2487 contract documents and manufacturer instructions for proper operation.

2488
2489 For engine-generator applications, perform system operational testing. Verify that the generator is not
2490 running and that the ATSS is set for automatic operation~~control switch in the AUTO position~~. Verify that
2491 the utility bus is energized, and manually close normal-side feeder breaker to energize the ATSS. Verify
2492 the position of the transfer switch and indication light statuses. Measure the input (normal) and output
2493 (load) voltages of the transfer switch. Check the phase rotation of the normal (utility) bus to the output
2494 bus of the transfer switch. Manually open the normal-side feeder breaker to the ATSS. Verify that the
2495 generation system starts, and that the ATSS transfers the load to the generation system. Verify the
2496 position of the transfer switch and indication light statuses. Measure the input (emergency) and output
2497 (load) voltages of the transfer switch. Check the phase rotation of the emergency (generator) bus to the

2498 output bus of the transfer switch. Manually close the normal-side feeder breaker to the ATS. Verify
2499 that the ATS transfers the load to the utility, and that generation systems cooldown, stop, and reset for
2500 automatic operation. Push the TEST switch to simulate a normal source failure. Verify that the ATS
2501 and generation systems operate properly.

2502
2503 Verify appropriate lubrication on moving current-carrying parts. Verify appropriate lubrication on
2504 moving and sliding surfaces.

2505
2506

2507 **5.5.30 Variable Frequency Drives (VFDs)**

2508
2509 Verify that the VFD rated output current is greater than the motor FLA. *NOTE: VFDs are current rated,*
2510 *not horsepower rated.*

2511
2512 Make sure that the nominal supply voltage, VFD rated voltage, and motor voltage are compatible.
2513 Check for proper jumper, screw, or switch settings for the given drive supply voltage parameters, if so
2514 equipped.

2515
2516 Ensure that VFDs are installed with an ambient temperature no greater than 40°C (104°F) with a humidity
2517 level from 10 to 90% non-condensing. Ensure that there is adequate clearance around VFDs for cooling
2518 in accordance with the manufacturer instructions. Verify that vent path openings are free from debris and
2519 that heat transfer surfaces are clean.

2520
2521 Verify that there are no power factor improvement capacitors installed on the VFD output between the
2522 VFD and the motor. *NOTE: Power factor capacitors connected on the VFD output will cause VFD*
2523 *damage.* Verify that there are no power factor improvement capacitors are installed within a feeder
2524 circuit length of 100m (300ft) of the VFD input if there is no line reactor or input filter installed on the
2525 VFD input. *NOTE: Upstream capacitors may cause nuisance overvoltage tripping of VFDs that do not*
2526 *have an input line reactor or input filter.*

2527
2528 For 460Vac or 575Vac installations, verify that the motor specification for the cable length and carrier
2529 frequency limitations are within recommended limits. *NOTE: A load reactor or an output filter may be*
2530 *needed, if recommended by the manufacturer.*

2531
2532 Verify that all electrical connections are tight. Verify correct connections of circuit boards, wiring,
2533 disconnects, and ribbon cables. Make sure that VFDs and all the electrical connections are free of debris.
2534

2535 Verify that the motor and the load rotate freely. Check for damaged bearings, correct belt tension, belt
2536 alignment, and/or shaft alignment.

2537
2538 Perform startup of VFDs in accordance with manufacturer instructions. Prior to starting the system,
2539 verify that the VFD system can be operated at full speed (60Hz) without causing damage to other
2540 equipment or endangering personnel.

2541
2542 *NOTE: VFDs will cause noise on neutral and ground conductors, and voltage fluctuations on phase*
2543 *conductors during normal operation. Additionally, VFDs induce motor bearing currents and shaft*
2544 *voltages that will cause pitting of the shaft and premature motor failure. Check motors for excessive*
2545 *voltages and currents. Install shaft voltage/current eliminators when needed in accordance with*
2546 *manufacturer instructions.*

2547

- 2548 Without applying power to the VFD, check the supply line phase-to-phase voltages. Phase voltages
2549 should be balanced within 3% of each other, and within 10% of the VFD nameplate rating.
2550
- 2551 Start and run the VFD while observing the test, metering, and fault indicators, if so equipped. Activate
2552 the various safety devices when possible, to ensure proper operation. Calibrate relays and test parameters
2553 for input phase loss protection, input overvoltage protection, output phase rotation, over-temperature
2554 protection, DC overvoltage protection, over-frequency protection, drive overload protection, and fault
2555 alarm outputs. Test the motor overload relay elements by injecting primary current through the overload
2556 circuit and monitoring trip time of the overload element.
2557
- 2558 Calibrate VFDs to the system's minimum and maximum speed control signals. Set adjustable
2559 parameters to match the settings provided. Verify that VFD overcurrent setpoints are correct for the
2560 application. If a VFD is used to operate multiple motors, verify individual motor overload element
2561 ratings are correct for their application. Apply minimum and maximum speed setpoints. Verify that
2562 setpoints are within limitations of the load coupled to the motor. Test and record output volts and amps
2563 while the drive is at 25%, 50%, and 100% of rated speed and attached load. Observe for balance and
2564 performance within manufacturer specifications.
2565
- 2566 Verify the phase rotation of the VFD output in both VFD mode and the BYPASS mode, if so equipped.
2567 Correct incorrect phase rotation in accordance with manufacturer instructions.
2568
- 2569 Record harmonic distortion at the VFD output, at the VFD input, and at the upstream source that
2570 supplies the VFD.
2571
- 2572 Check and program all the necessary software parameters such as acceleration time, deceleration time,
2573 application (constant torque, variable torque), carrier frequency, motor voltage, and motor overload
2574 protection level in accordance with manufacturer instructions. *NOTE: Incorrect software programming*
2575 *may result in equipment damage or failure.* Record any changes to the software parameters for future
2576 reference.
2577
- 2578 Perform operational tests by initiating control devices. Slowly vary VFD speed between minimum and
2579 maximum speeds. Observe the motor and load for unusual noise or vibration. Program VFDs to skip
2580 frequencies that cause excessive noise or vibration. Verify proper operation of VFDs from remote
2581 start/stop and speed control signals.
2582
- 2583 Start the motor load with the VFD in BYPASS mode, if so equipped, to ensure that upstream overcurrent
2584 protection devices do not trip for motor inrush current with the drive in BYPASS mode.
2585
2586
- 2587 **5.5.31 AC Synchronous Motors and Generators**
2588
- 2589 Check that the installation is complete. Inspect for physical damage. Check for loose items such as shaft
2590 keys and couplings. Inspect air baffles, filter media, cooling fans, slip rings, brushes, and brush rigging.
2591 Slip ring wear and brushes should be within manufacturer tolerances for continued use. Brush rigging
2592 should be intact.
2593
- 2594 Check all connections for tightness and proper insulation.
2595
- 2596 Uncouple the motor from the load (drive machinery), and manually rotate to verify that the motor rotates
2597 freely and is free from interference.

- 2598
2599 Verify the application of appropriate lubrication and lubrication systems.
2600
- 2601 Measure the resistance of the machine-field winding, exciter-stator winding, exciter-rotor windings, and
2602 field discharge resistors.
2603
- 2604 Prior to energizing, apply voltage to the exciter supply and adjust the exciter-field current to the
2605 nameplate value.
2606
- 2607 Verify that the field application timer and the enable timer for the power-factor relay have been tested and
2608 set to the motor drive manufacturer recommended values, if applicable.
2609
- 2610 Perform phase-to-phase stator resistance testing on machines rated 2300 volts and greater. Perform
2611 resistance tests on resistance temperature detector (RTD) circuits, if so equipped. Verify that resistance
2612 temperature detector (RTD) circuits conform to drawings.
2613
- 2614 Perform insulation-resistance test on insulated bearings in accordance with manufacturer instructions.
2615
- 2616 Perform insulation-resistance tests and dielectric absorption tests (polarization index and dielectric
2617 absorption ratio) on the main rotating field winding, the exciter field winding, and the exciter-armature
2618 winding in accordance with ANSI/IEEE Standard 43 and in accordance with manufacturer instructions.
- 2619 • For motors rated 200 HP and less, and rated 600V and less, perform insulation resistance and
2620 dielectric absorption testing.
 - 2621 • For motors rated more than 200 HP, and rated from 600V to 2400 V, perform insulation
2622 resistance testing and calculate dielectric absorption ratio and polarization index.
 - 2623 • For motors with ratings more than 200HP and more than 2400V, perform insulation resistance
2624 testing and calculate dielectric absorption ratio and polarization index, and perform high-potential
2625 testing.
- 2626 See Annex A for additional guidance. Perform tests on armature and rotating or stationary field windings.
2627 Disconnect the neutral connection on the stator, and test each winding with respect to the other windings
2628 and ground. Perform high-potential testing on each phase separately with the other phases and the
2629 winding temperature detectors grounded, if so equipped. Disconnect any capacitors and surge arrestors
2630 during testing.
2631
- 2632 Momentarily energize (bump) motors to verify proper phase rotation.
2633
- 2634 Perform vibration monitoring on all rotating equipment greater than 7-1/2 HP (or smaller if highly critical
2635 to operations), including motors, pumps, turbines, compressors, engines, bearings, gearboxes, agitators,
2636 fans, blowers, and shafts, as applicable. Conduct all tests at normal operating speed at maximum load
2637 conditions. The motor must meet the applicable vibration criteria as specified in Tables 3 and 4.
2638

Table 3 Motor Vibration Criteria

Frequency (X RPM) Motor Component	Maximum Amplitude (in/sec Peak)	Maximum Amplitude (mm/sec Peak)
Overall	0.1	2.5
0.4 – 0.5	Not detectable	
1X	See Motor Balance Specifications	
2X	0.02	0.5
Harmonics (NX)	Not detectable	
Roller Element Bearings	Not detectable	
Side Bands	Not detectable	
Rotor Bar/Stator Slot	Not detectable	
Line Frequency (60 Hz)	Not detectable	
2X Line Frequency (120 Hz)	0.02	0.5

Table 4 Motor Balance Specifications

Motor Speed (RPM)	Special Application		Standard Application	
	(in/sec Peak)	(mm/sec Peak)	(in/sec Peak)	(mm/sec Peak)
900	0.02	0.5	0.08	2.0
1200	0.026	0.66	0.08	2.0
1800	0.04	1.0	0.08	2.0
3600	0.04	1.0	0.08	2.0

2639
2640
2641
2642
2643
2644
2645
2646

Perform laser alignment on all shaft coupled machines (see Figure 1). All shaft-to-shaft center line alignments should meet the requirements of Table 5 unless more precise tolerances are specified by the machine manufacturer. The tolerances specified in Table 5 are the maximum allowable deviations from Zero-Zero Specifications or alignment target specifications (i.e., an intention targeted offset and/or angularity). Figure 2 illustrates the concept of offset and angular motor alignment.





Figure 1. Coupled Shafts Alignment

2647
2648
2649
2650
2651

Table 5 Coupled Shaft Alignment Tolerance Values			
	RPM	Tolerance Specification	
Soft Foot	All	<0.0508 mm (0.002 inch) at each foot	
		Horizontal & Vertical Parallel Offset per 25.4 mm (12 inches) of Spacer Length	Angularity/Gap mm/254 mm (1 inch/10 inches) Coupling Diameter
Short Couplings	<1000	1.2700 mm (0.005 in)	0.3810 mm (0.015 in)
	1200	1.0160 mm (0.004 in)	0.2540 mm (0.010 in)
	1800	0.7620 mm (0.003 in)	0.1270 mm (0.005 in)
	3600	0.5080 mm (0.002 in)	0.0762 mm (0.003 in)
	7200	0.2540 mm (0.001 in)	0.0635 mm (0.0025 in)
Couplings with Spacers	<1000	0.0508 mm (0.0020 in)	
	1200	0.0381 mm (0.0015 in)	
	1800	0.0254 mm (0.0010 in)	
	3600	0.0127 mm (0.0005 in)	
	7200	0.0076 mm (0.0003 in)	

2652



2653
 2654
 2655
 2656
 2657
 2658
 2659
 2660
 2661

Figure 2. Offset and Angular Motor Alignment

Upon startup, verify the absence of unusual mechanical or electrical noise and signs of overheating.

Verify proper operation of machine space heaters, if applicable.

Perform a vibration test.

2662

2663 **5.5.32 AC Induction Motors and Generators (Alternators)**

2664

2665 Inspect air baffles, filter media, cooling fans, slip rings, brushes, and brush rigging. Verify that resistance
2666 temperature detector (RTD) circuits conform to drawings, if so equipped. Verify that metering or
2667 relaying devices utilizing RTDs have the correct rating.

2668

2669 Verify the correct application of appropriate lubrication and lubrication systems.

2670

2671 Verify the absence of unusual mechanical or electrical noise and signs of overheating during initial test
2672 run.

2673

2674 Perform insulation-resistance tests and dielectric absorption tests (polarization index and dielectric
2675 absorption ratio) on the main rotating field winding, the exciter field winding, and the exciter-armature
2676 winding in accordance with ANSI/IEEE Standard 43 and in accordance with manufacturer instructions.

2677

- For motors rated 200 HP and less, perform insulation resistance testing and calculate the dielectric absorption ratio.

2678

- For motors rated more than 200 HP, perform insulation resistance testing and calculate polarization index.

2679

- For motors rated more than 1000HP and more than 4000V, perform insulation resistance and dielectric absorption testing, calculate polarization index, and perform high-potential testing.

2680

2681 See Annex A for additional guidance. Perform tests on armature and rotating or stationary field windings.

2682

2683 Disconnect the neutral connection on the stator, and test each winding with respect to the other windings
2684 and ground. Perform high-potential testing on each phase separately with the other phases and the
2685 winding temperature detectors grounded, if so equipped. Disconnect any capacitors and surge arrestors
2686 during testing.

2687

2688

2689 Perform phase-to-phase stator resistance testing.

2690

2691 Perform insulation-resistance testing on the bearing pedestal in accordance with manufacturer
2692 instructions.

2693

2694 Perform resistance tests on RTDs, if so equipped.

2695

2696 Verify proper operation of the motor space heater, if applicable.

2697

2698 Momentarily energize (bump) motors to verify proper phase rotation.

2699

2700 Measure the running current and evaluate relative to load conditions and nameplate full-load amperes.

2701

2702

2703 **5.5.33 DC Motors and Generators**

2704

2705 Inspect baffles, filter media, cooling fans, slip rings, brushes, and brush rigging.

2706

2707 Verify the correct application of appropriate lubrication and lubrication systems.

2708

2709 Inspect the commutator and tachometer generator.

2710

2711 Verify the absence of unusual mechanical or electrical noise and signs of overheating during initial test

2712 run.

2713

2714 Verify that resistance temperature detector (RTD) circuits conform to drawings, if so equipped. Verify
2715 that metering or relaying devices utilizing RTDs have the correct rating.

2716

2717 Perform insulation-resistance and dielectric absorption tests (polarization index and dielectric absorption
2718 ratio) on the main rotating field winding, the exciter field winding, and the exciter-armature winding in
2719 accordance with ANSI/IEEE Standard 43 and in accordance with manufacturer instructions. See Annex
2720 A for additional guidance.

2721 • For motors rated 200 HP and less, perform insulation resistance testing and calculate the
2722 dielectric absorption ratio.

2723 • For motors rated more than 200 HP, perform insulation resistance testing and calculate
2724 polarization index.

2725

2726 Perform an insulation-resistance test on the bearing pedestal in accordance with manufacturer
2727 instructions. Pedestal bearing insulation resistance must not be less than 1.0 megohm at 500 volts DC.

2728

2729 Perform resistance tests on RTDs, if so equipped.

2730

2731 Verify proper operation of the motor space heater, if applicable.

2732

2733 Measure armature running current and field current or voltage. Compare to nameplate.

2734

2735

2736 **5.5.34 Battery Systems**

2737

2738 Torque battery rack connections in accordance with manufacturer instructions. Inspect battery racks and
2739 insulating covers for physical damage, loose connections, cracking, dielectric leaks, dirt, corrosion, and
2740 seismic parts and spacers.

2741

2742 Check DC power, control power, and battery connections including cell-to-cell, tier-to-tier, rack-to-rack,
2743 and UPS to battery module connections, if applicable, for correct polarity.

2744

2745 Check battery jars and covers for cracking, distortion, dielectric leaks, dirt, and corrosion. Inspect jar and
2746 post seals. Check electrolyte levels, if applicable. Check vented lead-acid batteries and vented nickel-
2747 cadmium batteries for clogged flame arresters. Inspect vented lead-acid battery cells, and check plates for
2748 cracks, sulfate, and hydration.

2749

2750 Measure and record the cell-to-cell and terminal connection resistance with a digital low-resistance
2751 ohmmeter. Remake connections having a resistance of more than 10 percent above the average.

2752

2753 Inspect terminals for loose or broken connections, and burned insulation. Check for liquid contamination
2754 (battery electrolyte and oil from capacitors). De-energize equipment and make corrections or repairs for
2755 any abnormal operating conditions in accordance with manufacturer recommendations.

2756

2757 Verify the presence of flame arresters, adequacy of battery support racks, mounting, anchorage,
2758 grounding, and clearances, ventilation of battery room enclosure, and existence and proximity of suitable
2759 eyewash equipment.

2760

2761 Measure the voltage drop across all battery cells and across all DC connections with a digital voltage

2762 meter. Set the voltage range of the meter to the maximum open-circuit voltage range of the connection.
2763 Investigate readings that deviate from other readings by 25 percent or more.

2764
2765 Perform a battery impedance test and record the results.

2766
2767 Energize and test batteries in accordance with contract documents and manufacturer instructions. Inspect
2768 all parts for evidence of overheating and evidence of physical damage, including worn insulation and
2769 corrosion, at each step during energization. Close the battery circuit breaker, and measure and record the
2770 battery charging voltage and current. Allow the batteries to charge for a minimum of 24 hours, or until
2771 the batteries are fully charged, whichever is less. Record the time. Measure and record the battery float
2772 voltage and current and rectifier/battery charger output voltage and current every 4 hours while charging.

2773
2774 After charging, check batteries for signs of vibration, and check vented lead-acid batteries for signs of
2775 excessive gassing. For vented (flooded) batteries, add electrolyte to batteries as required to fill cells up to
2776 the bottom of the high-level line using manufacturer recommended materials and methods. Equalize non-
2777 valve regulated batteries in accordance with manufacturer instructions.

2778
2779 Verify that the batteries are fully charged and are on float charge. Measure and record the float voltage
2780 and charging current.

2781
2782 After charging batteries, measure each cell voltage and total battery voltage with the charger in the float
2783 mode of operation. Measure ripple current, specific gravity, electrolyte temperature, electrolyte fill level,
2784 overall float voltage measured at the battery terminals, charger output current and voltage, ambient
2785 temperature, condition of ventilation and monitoring equipment, and temperature of the negative terminal
2786 of each cell of the battery.

2787
2788 Load test batteries in accordance with manufacturer instructions. The values for discharge time and end
2789 point voltage should be selected from the battery manufacturer published ratings, and the values used for
2790 the acceptance test should be approximately the same as that of the intended application. The discharge
2791 rate should be at a constant current or constant power load equal to the selected manufacturer rating of the
2792 battery. Set up a load suitable for the test along with the necessary instrumentation to maintain the test
2793 discharge rate as determined above. Disconnect the charging source, connect the load to the battery to
2794 begin the test, and track the time, continuing to maintain the selected discharge rate. If the charging
2795 source cannot be disconnected, decrease the current being drawn by the load to compensate for the
2796 current being supplied to the battery by the charging source. Read and record the individual cell voltages
2797 and the battery terminal voltage with the load applied at the beginning and at the completion of the test
2798 and at intervals specified in contract documents or as recommended by the manufacturer. Take a
2799 minimum of three sets of readings. Take individual cell voltage readings between respective posts of like
2800 polarity of adjacent cells so as to include the voltage drop of the intercell connectors. Maintain the
2801 discharge rate and record the elapsed time at the point when the battery terminal voltage decreases to a
2802 value equal to the minimum average voltage per cell as specified by the design of the installation times
2803 the number of cells. Upon completion of testing, inspect bus bar bolts, repair and re-torque to
2804 specifications as necessary. Replace any failed batteries or bus bars and note on the record of the test.

2805
2806 Remove and dispose of empty, partially full, and excess acid drums, including shipping containers and
2807 obsolete batteries, in accordance with local laws and regulations regarding disposal of hazardous material.
2808 Do not dispose of batteries in a fire.

2809
2810

2811 **5.5.35 Battery Chargers**

2812
2813 Verify that the battery charger is compatible with the type and configuration of the battery plant. Check
2814 the settings of the charger and calibrate in accordance with manufacturer instructions to match the float
2815 and equalizing levels required by the batteries.

2816
2817 Inspect filter and tank capacitors.

2818
2819 Verify proper operation of cooling fans. Clean filters if provided.

2820
2821 Before connecting the battery charger to the battery, measure and record the battery charger output
2822 voltage. Verify proper operation of all charger functions and alarms. Verify proper polarity of the battery
2823 charger and the battery plant.

2824
2825 Upon energizing the battery charger, verify float voltage, equalization voltage, and high voltage shutdown
2826 settings. Verify the current limit. Verify correct load sharing of parallel battery chargers. Verify the
2827 calibration of meters. Verify the proper operation of alarms. Measure and record the input and output
2828 voltage and current. Measure and record AC ripple current and/or the voltage imposed on the battery.
2829 Perform full load testing of the charger.

2830

2831

2832 ***5.5.36 Flooded Lead Acid Batteries***

2833

2834 Verify that the battery room/area ventilation system is operable. Verify the existence and proximity of
2835 suitable eyewash equipment. Verify electrolyte levels. Measure electrolyte specific gravity and
2836 temperature levels. Verify the presence of flame arresters. Verify the adequacy of battery support racks,
2837 mounting, anchorage, seismic supports, if applicable, and clearances. Inspect the spill containment
2838 installation, if applicable. Verify the application of an oxide inhibitor on battery terminal connections.

2839

2840 Measure the charger float and equalizing voltage levels. Adjust charger settings to the battery
2841 manufacturer recommended settings. Verify all charger functions and alarms. Measure each cell voltage
2842 and total battery voltage with the charger energized and in the float mode of operation. Measure intercell
2843 connection resistances. Measure the battery system voltage from positive to ground and negative to
2844 ground.

2845

2846

2847 ***5.5.37 VRLA Batteries***

2848

2849 Verify that the battery room/enclosure ventilation system is operable. Verify existence and proximity of
2850 suitable eyewash equipment. Verify adequacy of battery support racks or cabinets, mounting, anchorage,
2851 seismic supports, if applicable, and clearances. Verify the application of an oxide inhibitor on battery
2852 terminal connections.

2853

2854 Measure negative post temperatures. Measure the charger float and equalizing voltage levels. Verify all
2855 charger functions and alarms. Measure each monoblock/cell voltage and total battery voltage with the
2856 charger energized and in the float mode of operation. Measure intercell connection resistances. Perform
2857 internal ohmic measurement tests.

2858

2859

2860 ***5.5.38 Uninterruptible Power Supply (UPS) Systems***

2861

- 2862 Coordinate UPS testing with generator/transfer switch testing, if applicable.
2863
- 2864 Verify electrical connections using the wiring schematic to ensure proper phasing and voltage
2865 connections. Check that the battery charger connections to the battery and the battery connections to
2866 the inverter have the correct polarity. Verify the proper operation of forced ventilation. Verify that the
2867 vents are clear, air inlets are not obstructed, and filters are in place.
2868
- 2869 Adjust programmable parameters in accordance with manufacturer instructions. Set the free running
2870 frequency of the oscillator.
2871
- 2872 Simulate critical malfunctions to test all warnings, alarms, and shut downs and to verify annunciation and
2873 protective device functions. Test alarm circuits. Test all electrical and mechanical interlock systems for
2874 correct operation and sequencing.
2875
- 2876 Verify synchronizing indicators for static switch and bypass switches, if so equipped. Test the static
2877 transfer from the inverter to bypass and back. Use the actual UPS load if possible without interrupting
2878 critical loads. Test DC undervoltage trip level on the inverter input breaker.
2879
- 2880 Measure and record the battery voltage. Measure and record the inverter output voltage and current.
2881
- 2882 Perform an infrared scan in accordance with Annex A.
2883
- 2884 See NECA 411 for additional guidance.
2885
2886
- 2887 **5.5.39 Lighting**
2888
- 2889 Perform operational tests on completed lighting systems, including testing all switches, controls, and
2890 emergency lights, switching ballasts, and batteries. Test the operation of lighting controls and integral
2891 components to ensure they respond appropriately to changing conditions and parameters, as specified.
2892
- 2893 Measure lighting levels in all areas to assure they meet the requirements specified in the contract
2894 documents. Demonstrate lighting levels at desk level after dark to ensure that they are not affected by
2895 daylight, and record readings.
2896
- 2897 Walk-test areas equipped with occupancy sensors to ensure that lights turn on and off automatically.
2898 Adjust time delay and sensitivity settings as needed. Verify proper occupant override operation, if
2899 applicable. Record blind spots or issues with occupancy sensors not performing properly.
2900
- 2901 For lighting control relay panels, verify that the time clock, if so equipped, has been programmed with
2902 correct lighting zones and correct on/off controls. Simulate time-changes to witness automatic light
2903 controls. Verify proper occupant override operation, if applicable. Record any issues observed during
2904 testing.
2905
- 2906 For daylight harvesting systems, test dimming controls during daylight hours when controls should
2907 automatically dim lighting. Verify that amperage changes in light fixtures are proportional to external
2908 light changes. Verify that light levels at the specified work plane remain within specified limits using a
2909 combination of daylight and dimmable lighting. Measure and record light levels in each room. Verify
2910 that all (and only) specified light fixtures are controlled by the system. Verify that dimming delays and
2911 ramp times are set and functioning so that changes in light fixture output are gradual, do not bother

2912 occupants, and comply with the specifications. Verify that dimming does not cause lower-than-specified
 2913 lighting levels in spaces with daylight harvesting. Verify that the controls and sensors are tamper-
 2914 resistant and not easily overridden or disabled by occupants. Verify that photo sensors are in appropriate
 2915 locations for the lights being controlled and are not affected by direct sunlight or obstructions (shadows).
 2916 Adjust system and component settings as needed in accordance with contract documents, drawings and
 2917 specifications, and in accordance with manufacturer instructions.

2918
 2919 See NECA/IESNA 500, NECA/IESNA 501, and NECA/IESNA 502 for additional guidance.
 2920

2921

2922 **5.5.40 System Testing**

2923

2924 Perform system functional testing upon completion of the acceptance tests on individual equipment and
 2925 components. Develop test parameters and perform tests for the purpose of evaluating the performance of
 2926 all related components and equipment, and their functioning as an integrated system within design
 2927 requirements and in accordance with manufacturer instructions.

2928

2929 Test interconnections of the electrical equipment with other systems, such as mechanical, security, and
 2930 fire alarm systems. If a building automation system (BAS) is installed, verify the overall system
 2931 functions, monitoring and control, including data points derived from or delivered to the electrical
 2932 system.

2933

2934 Verify the proper operation of electrical equipment and devices under load. Coordinate testing as
 2935 needed to allow for testing the electrical system while mechanical systems are running.

2936

2937

2938 **5.5.41 Medium and High-Voltage Surge ~~Arresters~~ Protective Devices (SPDs)**

2939

2940 Inspect ~~SPDs~~ arresters for correct mounting and adequate clearances. Verify that arresters are clean.
 2941 Verify that the ground lead on each device is individually attached to a ground bus or grounding
 2942 electrode. Verify that the stroke counter, if present, is correctly mounted and electrically connected.

2943

2944 Test the ground connection for continuity. Measure the resistance of the ground connection. The
 2945 resistance between the arrester ground terminal and the grounding system should be less than 0.5 Ohm.

2946

2947 Perform insulation-resistance testing at voltage levels in accordance with the manufacturer instructions.
 2948 See Annex A for additional guidance.

2949

2950

2951 **5.5.42 Low-Voltage Surge Protective Devices (SPDs)**

2952

2953 Inspect SPDs ~~for correct mounting and adequate clearances~~ to ensure conductor length from the SPD to
 2954 the bonding location is as short as possible and does not exceed the SPD's manufacturer's maximum
 2955 length requirement. If manufacturer's requirements are unknown, ensure length does not exceed 36
 2956 inches with no sharp bends or coils. If present, verify that the SPD's ground lead on each device is
 2957 individually attached ~~bonded~~ to a grounded bus or ground electrode. Verify that the stroke counter, if
 2958 present, is correctly mounted and electrically connected. ~~NOTE: When SPDs are not connected directly~~
 2959 to equipment bus work but have lead wires, excessive length and sharp bending of those wires can reduce
 2960 the SPD effectiveness. Where practicable, keep length of leads less than 24-inches.

2961

2962 ~~If present, Test the SPD's ground connection for continuity. Measure the resistance of the~~
 2963 ~~ground connection between the SPD's ground terminal (if accessible) and the grounding system. The~~
 2964 ~~resistance between the arrester ground terminal and the grounding system should be less than 0.5 Ohm.~~
 2965 ~~*NOTE: Not all SPD's utilize a common ground conductor (common mode).*~~

2966
 2967 ~~Perform insulation-resistance testing in accordance with manufacturer instructions. Perform an insulation~~
 2968 ~~power factor test. Power factor tests should indicate similar dielectric loss between similar arrests. See~~
 2969 ~~Annex A for additional guidance.~~

2970

2971

2972

5.5.43 Capacitors

2973

2974

2975

2976

2977

2978

2979

2980

2981

2982

2983

2984

2985

2986

2987

2988

2989

2990

2991

2992

5.5.44 Dry-Type Reactors (Shunt and Current-Limiting)

2993

2994

2995

2996

2997

2998

2999

3000

3001

3002

3003

3004

3005

3006

3007

3008

3009

3010

3011

5.5.45 Liquid-Filled Reactors (Shunt and Current-Limiting)

Verify the settings and operation of all temperature devices, if applicable. Verify that cooling fans and pump motors have correct overcurrent protection, if applicable. Verify proper operation of all alarm, control, and trip circuits from temperature and level indicators, pressure relief devices, and fault pressure relays, if applicable. Verify correct liquid level in all tanks and bushings. Verify that positive pressure is maintained on nitrogen-blanketed reactors. Verify that tap connections are as specified, if applicable.

Perform winding-to-ground insulation-resistance tests. Apply voltage in accordance with manufacturer published data. See Annex A for additional guidance. Calculate the polarization index. Perform

3012 insulation power-factor or dissipation-factor tests on windings in accordance with the test equipment
 3013 manufacturer published data. Perform power-factor or dissipation-factor or hot collar watts-loss tests on
 3014 bushings in accordance with the test equipment manufacturer published data. Measure winding
 3015 resistance. Measure the percentage of oxygen in the nitrogen gas blanket, if applicable.
 3016

3017 Remove a sample of insulating liquid in accordance with ASTM D-923. Test the sample for:

- 3018 • Dielectric breakdown voltage: ASTM D-877 and/or ASTM D-1816.
- 3019 • Acid neutralization number: ASTM D-974.
- 3020 • Specific gravity: ASTM D-1298.
- 3021 • Interfacial tension: ASTM D-971 or ASTM D-2285.
- 3022 • Color: ASTM D-1500.
- 3023 • Visual Condition: ASTM D-1524.
- 3024 • Water in insulating liquids: ASTM D-1533. (Required on equipment rated 25 kV or higher, and
 3025 on all silicone-filled units.)
- 3026 • Measure power-factor or dissipation-factor in accordance with ASTM D-924.
- 3027 • Remove a sample of insulating liquid in accordance with ASTM D-3613 and perform dissolved-
 3028 gas-analysis in accordance with ANSI/IEEE C57.104 or ASTM D-3612.

3031 **5.6 Deferred and Seasonal Testing**

3032
 3033 If any check or test cannot be completed due to the need for seasonal testing, weather conditions, building
 3034 structure, required occupancy levels, or other testing factor where system loadings are closer to the
 3035 system design criteria, or other deficiency, the execution of checklists and functional testing may be
 3036 delayed until after Substantial Completion, but before the expiration of the warranty period, upon
 3037 approval of the CA and owner. Perform these tests and checks as soon as conditions permit adequate
 3038 testing.
 3039

3040 Perform and document the specified testing and the results. Correct deficiencies identified during
 3041 deferred and seasonal testing. Update record documents, O&M manuals, as-build drawings, and other
 3042 commissioning documents as needed for any modifications made during deferred or seasonal testing.
 3043
 3044

3045 **6. Recording and Documenting Performance**

3046
 3047 Documentation is an essential component of the commissioning process. Record and collect all formal
 3048 and informal communications during the commissioning process. Document all pre-functional and
 3049 functional performance checks and tests. Submit documentation in the format(s) as required in contract
 3050 documents.
 3051
 3052

3053 **6.1 Documentation**

3054
 3055 *NOTE: Commissioning, including start-up testing, acceptance testing, integrated system testing, and*
 3056 *operational tune-ups and adjustments, is the process by which the proper operation and sequence of*
 3057 *operation of electrical equipment is validated, in addition to developing baseline criteria by which future*
 3058 *trend analysis can identify equipment deterioration. These baseline tests are compared with later tests*
 3059 *and the results of routine maintenance to identify any downward trend in equipment and system*

3060 *performance. As such, it is vital to maintain complete and accurate records of commissioning and*
 3061 *maintenance activities.*

3062

3063 Commissioning documentation includes, but is not limited to:

- 3064 • Approved submittals, testing, balancing, and calibration reports for the equipment, sub-systems,
3065 and systems being commissioned.
- 3066 • All approved shop drawings of electrical equipment. Fold full-size sheets as required to fit in
3067 binders.
- 3068 • All pre-functional performance test checklists, signed by the responsible personnel, organized
3069 by system and sub-system.
- 3070 • All verification and functional performance test checklists/results, signed by the responsible
3071 personnel, organized by system and sub-system.
- 3072 • Completed as-built drawings signed by the contractor.
- 3073 • Copies of the operation and maintenance (O&M) manuals.

3074

3075

3076 **6.2 Non-Conformance Items**

3077

3078 *NOTE: In general, the A/E is the final interpretive authority regarding technical non-compliance issues*
 3079 *or deficiencies (compared with Design Intent or Basis of Design (BOD) documents) and their resolution*
 3080 *(in accordance with the Design Intent or Basis of Design (BOD) documents).*

3081

3082 *NOTE: In general, the owner is the ultimate decision authority in resolving deficiencies or issues of non-*
 3083 *conformance. The owner may decide whether modifications are required to correct deficiencies, or*
 3084 *whether tests will be accepted as submitted. If corrective work is performed, the owner may determine*
 3085 *whether tests will be repeated and a revised report submitted.*

3086

3087 Non-conformance items or deficiencies may be identified at any point during the commissioning process.
 3088 All deficiencies should be recorded in a comprehensive log that is maintained by the CA, is continuously
 3089 updated, and is periodically reviewed by the entire commissioning team.

3090

3091 Deficiencies identified during commissioning should be documented on standardized forms and/or
 3092 checklists used to document that particular phase of commissioning for the specific equipment or system.
 3093 Minor deficiencies that can be corrected during the normal course of performing testing and
 3094 commissioning procedures should be corrected at that time with appropriate notations made on the forms
 3095 and/or checklists.

3096

3097 Deficiencies or non-conformance items that cannot be corrected during the normal course of performing
 3098 testing and commissioning procedures should be documented on a standardized Resolution Tracking
 3099 Form or Non-Conformance Form that summarizes each deficiency and outlines possible options for
 3100 resolving the deficiency, along with recommending a preferred option for resolution, that is submitted to
 3101 the A/E for review. *NOTE: The Resolution Tracking Form or Non-Compliance Form should contain a*
 3102 *Statement of Correction that is signed after resolution of the deficiency, and to certify that the equipment*
 3103 *or system is ready for retesting.*

3104

3105

3106 **7. Operating and Maintenance (O&M) Manuals**

3107

3108 Operating and Maintenance (O&M Manuals) typically include, but are not limited to, the following:

- 3109 • System descriptions, including narratives of the theory of operation, overall system layout,
- 3110 description of major components, interconnections with utilities and other systems, description of
- 3111 control system layout and operation, identification of unusual features or functions, and major
- 3112 safety precautions.
- 3113 • Manufacturer installation, start-up, and operating instructions.
- 3114 • Control sequences describing start-up, all modes of operation, and shut down.
- 3115 • Troubleshooting procedures.
- 3116 • References to drawings, schematics, sequences of operation, and other information included as
- 3117 part of the construction contract drawings and specifications that show the system configuration
- 3118 and layout and equipment arrangements and items of control, as appropriate.
- 3119 • Spare parts lists.
- 3120 • Manufacturer, vendor, supplier, and sub-contractor 24-hour contact information.
- 3121 • Approved and corrected shop drawings, such as wiring, control, and one-line diagrams, and
- 3122 marked-up catalog data.
- 3123 • Owner-contracted tests, if any.
- 3124 • Factory testing reports, if any.
- 3125 • Field test reports, checklists, and forms.
- 3126 • Full warranty information, including clearly identifying all responsibilities of the Owner
- 3127 to keep the warranty in force.
- 3128 • Copies of the installation, start-up, and checkout materials that are supplied with and shipped
- 3129 inside equipment, if any.
- 3130 • Forms and checklists completed in the field by factory or field technicians.
- 3131 • Preventive maintenance procedures including recommended frequency for each preventive
- 3132 maintenance task, such as cleaning, inspection, lubrication, and scheduled overhauls. Group
- 3133 tasks and sort by frequency, such as daily, weekly, quarterly, and annually.
- 3134

3135 The Commissioning Authority (CA) should review the O&M manuals early in the commissioning
 3136 process to become familiar with the equipment, sub-systems, and systems being tested, and to use in
 3137 developing commissioning and test procedures.

3138
 3139 Organize O&M Manuals by each major system. Submit O&M Manuals in digital formats when
 3140 permitted. For hard copies, submit O&M Manuals in three-ring binders.

3141
 3142 All information included in the final O&M Manuals, including equipment schedules, manufacturer
 3143 literature, and drawings, must represent the as-built condition of systems and equipment. Include all data
 3144 concerning changes made during construction.

3145
 3146 Each section must include the information required in the appropriate section of the specifications plus
 3147 any additional information necessary for the owner's personnel to successfully operate and maintain the
 3148 systems and equipment covered in that section.

3149 **8. Training**

3150
 3151
 3152
 3153 Conduct comprehensive training for the owner's operating and maintenance (O&M) personnel in the
 3154 operation, maintenance, and troubleshooting of all commissioned systems and equipment. Ensure that
 3155 training meets any requirements listed in the contract documents. Provide video/audio recording of the
 3156 training as a record document and for use for future training.

3157

3158 Interview the owner's O&M personnel to determine any special training needs, to verify areas in which
3159 training will be most valuable, and to determine how rigorous training should be for each piece of
3160 commissioned equipment.

3161

3162 In general, vendors should be responsible for providing training on their respective equipment. Vendors
3163 should submit a written training plan for review and approval by the owner's representative and the CA
3164 prior to training.

3165

3166 Use approved O&M manuals as training resources whenever possible.

3167

3168

(This Annex is not a part of the Standard)

Annex A: Electrical Testing Procedures

A.1 General

Perform electrical testing in accordance with test equipment manufacturer instructions. Use test equipment of suitable ratings and sensitivity. Follow manufacturer instructions for testing equipment and conductors. Observe all manufacturer warning labels. See Section 3 for additional safety precautions.

Limit test voltages to prevent damage to equipment and conductors, to prevent damage to joints (tees, taps and splices), terminations, attached equipment, and accessories that are not rated to withstand test voltages, and to prevent voiding equipment warranties. Disconnect surge protective devices, potential transformers, and sensitive electronic components from equipment under test to prevent damage.

Maintain a permanent record of all test results. Record wet- and dry-bulb temperatures or relative humidity and temperature.

A.2 Vibration Monitoring

Use a vibration data collector with the following minimum requirements:

- Minimum of 400 lines of resolution
- Dynamic range greater than 70dB
- Frequency response of 5Hz-10kHz (300 to 600,000 cycles per minute (cpm))
- Capability to perform ensemble averaging
- Use of a Hanning window
- Auto-ranging frequency
- Minimum amplitude accuracy over the selected frequency range of $\pm 20\%$ or ± 1.5 dB

The vibration data collector device must use either a stud-mounted or a low mass rare earth magnet-mounted accelerometer. Do not use hand-held accelerometers. The mass of the accelerometer and its mounting must have minimal influence on the frequency response of the system over the selected measurement range.

Sound discs must be a minimum of 1 inch in diameter, manufactured of a magnetic stainless steel, such as alloy 410 or 416, have a surface finish of 32 micro-inches rms, and be attached by tack weld, be stud mounted, or be epoxy glued.

A.3 Contact Resistance

Inspect bolted electrical connections for high resistance using a low-resistance ohmmeter. Compare bolted connection resistances to values of similar connections. Microhm or millivolt drop values should not exceed the high levels of the normal range as indicated in manufacturer-published data. If manufacturer data is not available, investigate any values which deviate from similar connections by more than 50 percent of the lowest value.

A.4 Infrared Scan

Perform infrared scanning in accordance with test equipment manufacturer instructions. Use an infrared scanning device designed to measure actual operating temperatures, or designed to detect significant deviations from surrounding conditions. Provide documentation of device calibration.

Provide supplemental barriers and safety precautions during infrared scanning to prevent accidental contact with exposed energized components. Use appropriate personal protective equipment (PPE).

De-energize equipment and conductors in accordance with established safety procedures. Remove accessible covers, plates, panels, weathershields, and doors of equipment, junction boxes, and pull boxes to reveal busing, conductors, terminations, joints, and other internal current-carrying components.

Energize equipment and conductors, and turn on all normal loads. Allow equipment and conductor to reach normal operating temperature.

Perform infrared scanning of all accessible current-carrying electrical components while conductors and equipment are energized and operating under normal to maximum load conditions, but not less than 40 percent of the rated capacity of the electrical equipment being inspected. *NOTE: Infrared scan results could be inconclusive if equipment and conductors are lightly loaded.*

Inspect distribution systems, equipment, and conductors with imaging equipment capable of detecting a minimum temperature difference of 1°C at 30°C. Equipment should detect emitted radiation and convert detected radiation to a visual signal.

Prepare a report identifying the equipment and conductors tested, and describing the results of the infrared scan. Include notations of deficiencies detected, causes of temperature differences, remedial actions taken, results from retesting after remedial actions, and inaccessible or unobservable areas and equipment. Maintain a permanent record of all infrared scan results to track electrical characteristics of equipment, conductors, terminations, and joints over time.

Temperature differences of 1°C to 3°C indicate possible deficiency and warrant investigation. Temperature differences of 4°C to 15°C indicate a deficiency; repair as time permits. Temperature differences of 16°C and above indicate a major deficiency that must be repaired immediately.

Consult equipment, conductor, termination, connector, accessories, and component manufacturers for repair or replacement recommendations if infrared scan results indicate overheating of components.

A.5 Insulation Power Factor

Use a power factor test set with the following minimum requirements:

- Test voltage range of 500V to 12 kV.
- Ability to perform UST, GST, and GST with guard tests.
- Readings for power factor, dissipation factor, capacitance, and watts-loss.
- Power factor/dissipation factor range of 0 to 200%.
- Capacitance measuring range of 0 to 0.20 pico-farads.

Perform an insulation power factor test on each winding of transformers in accordance with the transformer manufacturer published data or the test equipment manufacturer published data. Correct

results to 20°C in accordance with test equipment manufacturer instructions. Compare results obtained to manufacturer factory test results. If manufacturer data is not available, acceptance tests results will serve as the baseline data for future reference. Investigate power factor test values more than 3-percent for dry-type transformers.

Perform a power factor test on transformer bushings that are equipped with power factor taps, and perform hot collar watts-loss test on filled bushings that are not equipped with power factor taps. Correct results to 20°C in accordance with test equipment manufacturer instructions. Maximum power factor of liquid-filled transformers corrected to 20°C must be in accordance with transformer manufacturer published data. Compare with test equipment manufacturer published data. Investigate bushing power factors and capacitances that vary from nameplate values by more than ten percent. Investigate any bushing hot collar watts-loss results that exceed the test equipment manufacturer published data.

A.6 Battery Impedance

Use a battery impedance test set with the following minimum requirements:

- Ability to test battery cells of up to 2500 amp-hour capacities
- Maximum battery test voltage of 25 Volts DC
- Impedance range of 0.0 to 100 milliohms
- Ability to test both lead-acid and nickel-cadmium batteries
- Test voltage stability of +/-0.1%
- Resistance accuracy of +/-5% at 1 megohm

A.7 Breaker Timing

Use a breaker timing test set with the following minimum requirements:

- Perform contact timing during breaker close, open, open-close, close-open, and open-close-open.
- Have a minimum of three dry contact inputs
- Have a minimum of two wet-input channels to monitor breaker secondary contacts
- Have a minimum resolution of + 0.0001 seconds over a one-second duration
- Have travel transducers capable of linear and rotary motion
- Be capable of slow close contact point measurement

A.8 Insulation Resistance Testing

Use an insulation resistance test set with the following minimum requirements:

- Test voltage increments of 500V, 1000V, 2500V, and 5000V DC
- Resistance range of 0.0 to 500,000 megohms at 500,000V DC
- A short-circuit terminal current of a minimum of 2.5 milliamps

Conduct tests of electrical equipment, sub-systems, and systems using normal procedures and requirements to ensure safety. Disconnect sensitive electronic equipment, such as surge protective devices (SPDs), before insulation resistance testing. Disconnect one side of transformers and coils before testing.

Insulation resistance measurements specified are the minimum acceptable values at an ambient

temperature of 16°C (60°F) with a relative humidity of less than 60-percent. Do not perform insulation resistance tests during times of high relative humidity. When insulation resistance measurements are taken at other than 16°C (60°F), convert quantities to equivalent values at 16°C (60°F).

Do not perform tests on outdoor equipment during inclement weather. Do not perform tests on direct burial ground conductors or on ground rods within a 48-hour period following rainfall.

During cable tests, station an individual at each point where cable has exposed connections.

Perform insulation-resistance testing from phase-to-ground and from phase-to-phase for equipment and conductors in accordance with the equipment and the test instrument manufacturer instructions. Measure insulation resistance of low-voltage circuit breakers, switches, and equipment phase-to-phase and phase-to-ground and across open poles. Isolate conductors and cables by opening switches or breakers at each end of cable before testing, when possible. *NOTE: Where conductors and cables are directly connected to equipment with no disconnecting means, test as connected; do not disconnect conductors or cables.* Ground equipment, conductors, and cable shields not being tested.

Do not exceed the voltage rating of the equipment and conductors under test. In general, perform insulation resistance testing using a test voltage of 1000V DC for 600 V rated insulation, and 500V DC for 300 V rated insulation. For transformers rated 600V and below, use a minimum voltage of 1000V DC. For transformers rated 601-5000V, use a minimum voltage of 2500V DC. For transformers rated above 5000V, use a minimum voltage of 5000V DC.

Measure insulation resistance at one minute following the application of the test voltage. Record the megohm values of each phase-to-ground and between each phase-to-phase, along with the description of the instrument, voltage level, humidity, temperature, time, and date of the test. Ground equipment and conductors at the completion of the test.

Compare test results with previous test results and with manufacturer data corrected for temperature variations using manufacturer recommended correction factors. Consult the equipment manufacturer published data for acceptable test results. If published data is not available, investigate any values which deviate from previous test results under similar conditions by more than 50 percent of the lowest value.

Insulation resistance should not be less than 2 megohms for circuits under 115V, 6 megohms between conductor and ground for 115V to 600V circuits with total single conductor length of 2500 feet and over, and not less than 8 megohms for 115V to 600V circuits with single conductor length of less than 2500 feet. For low-voltage, air-insulated and insulated case circuit breakers, insulation resistance should not be less than fifty (50) megohms.

When insulation resistance measurements fall below the specified minimum values at 16°C (60°F), apply heat and dry equipment and conductors in accordance with manufacturer instructions, subject to the approval of the CA. If drying is to be done by applying an electric potential to the equipment, do not exceed the continuous voltage or current ratings of the equipment being dried, either directly or by induction.

A.8.1 Dielectric Absorption and Polarization Index

Perform a dielectric absorption test for rotating machinery, motors and alternators, and dry-type transformers from winding to winding and winding to ground for ten minutes. Apply test voltage for 10

minutes or more to develop the dielectric-absorption characteristic.

Plot insulation resistance against time to determine the presence of moist or dirty windings. A steady rising curve is indicative of clean, dry windings. A quickly flattening curve is the result of leakage current through or over the surface of the winding and is indicative of moist or dirty windings.

If facilities are not available for a 10-minute test, calculate the polarization index by taking insulation resistance readings at 30 and 60 seconds. The ratio of the 60-to-30-second or the 10-to-1-minute ratio will serve as an indication of the winding condition.

The dielectric absorption ratio or polarization index should be greater than 1.0 and should be recorded and maintained for future reference. For DC motors and generators, investigate dielectric absorption ratios less than 1.4 and polarization index ratios less than 2.0 for Class B insulation and Class F insulation. Compare to manufacturer factory test results. If manufacturer data is not available, acceptance tests results will serve as baseline data for future reference.

A.9 High-Potential Acceptance Testing (DC High-Potential and Very Low Frequency (VLF) AC High-Potential Testing)

NOTE: DC high-potential or overpotential testing can cause insulation failure and should be used with caution. Complete all insulation resistance testing prior to high-potential testing. Review insulation resistance test results to determine the suitability for high-potential testing. Do not perform DC high-potential tests until insulation-resistance levels are raised above minimum levels.

Provide supplemental barriers and safety precautions during high-potential testing to prevent accidental contact with exposed energized components. Clean and dry equipment found in a wet or dirty condition before performing high-potential testing.

Humidity, wind, and surface conditions strongly affect the results of DC high-potential testing. Do not perform high-potential tests during times of high relative humidity. Follow manufacturer instructions for performing high-potential testing of equipment and conductors. Follow the test equipment manufacturer instructions. Use the lowest possible test voltages as recommended by the equipment or conductor manufacturer and the test equipment manufacturer.

Check the high-potential test set for proper operation. Ensure that the input voltage to the test set is regulated. Ensure that DC high-potential test equipment only measures the leakage current associated with the equipment or conductor under test and does not include the internal leakage of the test equipment. Follow the test equipment manufacturer instructions for connecting leads and performing tests.

Apply the test voltage for a minimum of 15 minutes. Graph microampere leakage versus time. Plot values every 30 to 60 seconds. Discontinue tests if erratic results are observed. Make notations including the data and time of testing, and the ambient temperature and relative humidity at the time of testing.

Consult the manufacturer for equipment and conductors that fail high-potential testing. Repair or replace equipment and conductors that fail high-potential testing in accordance with manufacturer instructions. Repeat high-potential testing in its entirety for equipment and conductors that are repaired or replaced.

A.9.1 DC High-Potential Testing

Apply the test voltage slowly in a minimum of five equal increments until maximum test voltage is reached, with no increment exceeding the conductor or equipment voltage rating, and with each voltage step being held for an equal interval of time long enough to allow the leakage current to reach stability, approximately 1 to 2 minutes. See Table A.9.1 for the maximum recommended DC high-potential test voltages. Record readings of leakage current at 30 seconds and one minute, and at one-minute intervals thereafter until the 15-minute test duration is met.

Table A.9.1 Recommended Maximum Voltages for DC High-Potential Testing

Rated Circuit Voltage (KV)	Test Voltage (kV)	
	100 % Insulation	133 % Insulation
5	25	35
8	35	45
15	55	65
25	80	96
28	85	100
35	100	125

Record leakage current in microamperes at the end of each interval before the voltage is raised to the next level. Plot test voltage versus leakage current on graph paper as testing progresses. *NOTE: A linear increase in leakage current is expected, and it should stabilize or decrease from the initial value at each step.* Calculate the resistance at each step. As long as the leakage current decreases or remains steady after it has leveled off, the test is considered satisfactory.

Any excessive or nonlinear increase in leakage current can indicate imminent insulation failure. If the leakage current starts to increase (excluding momentary increases due to test equipment power supply disturbances), extend the test to determine whether the rising trend continues. Increasing leakage current will result in the complete breakdown of already-damaged insulation, evidenced by an abrupt increase in leakage current accompanied by a sharp decrease in test voltage. In this case, discontinue the test and consult the manufacturer for recommendations. *NOTE: This is characteristic of approximately 80% of all DC high-potential test failures on cables with elastomeric insulation.*

At any step where the calculated leakage resistance decreases approximately 50 percent or more of that of the next lower voltage level, discontinue the test to prevent insulation failure and to retain the equipment in a serviceable condition until its replacement can be scheduled.

Sudden failure or flashover can occur if the insulation is already completely or nearly punctured. Voltage increases until it reaches the sparkover potential of the air gap length, then flashover occurs. *NOTE: Polyethylene cables exhibit this characteristic for all failure modes.*

After recording all measurements, rapidly turn the test equipment to zero volts and monitor cable voltage. Record the decaying voltage every 15 seconds for 90 seconds, and then every 60 seconds until the charge is down to 10% or less of the test voltage, then solidly ground the cable. Remove the test lead for connection to the next conductor. After testing, ground cables for a minimum of four times as long as the

test voltage was applied during the high-potential tests to assure complete discharge, but not less than 30 minutes.

A.9.2 Very Low Frequency (VLF) AC High-Potential Testing

Apply the test voltage for a minimum of 30 minutes. See Table A.9.2 for the maximum recommended VLF test voltage levels. If the VLF testing frequency is adjusted from a nominal 0.1 Hz, such as to compensate for very long cables, adjust the test time accordingly.

Table A.9.2 Recommended Maximum Voltages for VLF AC High-Potential Testing

Rated Circuit Voltage (kV)	Installation Test Maximum RMS Voltage (Phase to Ground)	Acceptance Test Maximum RMS Voltage (Phase to Ground)
5	9	10
8	11	13
15	18	20
25	27	31
35	39	44

Several VLF test waveforms are possible. In the absence of other recommendations, perform VLF testing using a smooth, load independent sinusoidal waveform (similar to that found in nominal 60 Hz AC power systems) with an optimized frequency held as close as possible to 0.1 Hz.

Multiple parallel conductors within each phase may be bolted together for testing purposes to reduce overall test times. If test results are questionable with parallel conductors, test each conductor separately.

Cable that has been VLF withstand tested is considered to have good insulation when no failure is detected during the withstand test and the percent standard deviation of Tan-Delta measurements at all test voltages is less than 0.02 (See Section A.10). Cable with a percent standard deviation of Tan-Delta measurements ~~is~~ greater than 0.02 should be tested further to determine the cause.

A.10 Tan-Delta (Dissipation Factor) Testing Using Very Low Frequency (VLF) Test Set

NOTE: Tan-Delta testing is used to evaluate overall cable condition and can be used to detect water trees in medium-voltage cable. Test results may not be accurate for cables exceeding 1,600 m (5,000 feet) in length.

Perform Tan-Delta testing only on shielded cables. *NOTE: Unshielded cables do not have a consistent reference to ground.*

Ensure that conductors are disconnected from equipment. Test only one conductor at a time. Disconnect parallel conductors.

Select the test voltage in accordance with manufacturer instructions. *NOTE: The test voltage, V_o , is typically calculated from the nominal system voltage, from phase-to-ground for wye-connected three-*

phase four-wire systems, and from phase-to-phase for delta-connected three-phase, three-wire systems. The test voltage may be lowered, such as when testing cables that are known to be degraded or when spare conductors are not available.

Tan-Delta testing is conducted from each conductor to ground in three steps of three minutes each, with readings taken at the end of each three-minute step, with an applied test voltage of 0.5 times V_o for Step 1, 1.0 times V_o for Step 2, and 1.5 times V_o for Step 3.

NOTE: Undamaged cable behaves like a capacitor with a 90° phase shift between the voltage waveform and the current waveform. Cable that is damaged or degraded will have increased leakage current resulting in a measured phase displacement of less than 90°.

Tan-Delta test results are typically that values increase with voltage level (higher Tan-Delta results at higher test voltages). Negative differences in Tan-Delta test results may indicate a faulty test procedure or may indicate significant defects with the cable, and further testing is recommended. Poor Tan-Delta test values typically indicate significant cable degradation of the overall cable.

Maintain a record of Tan-Delta measurements to track cable electrical characteristics over time.

A.11 Partial Discharge Testing

Partial Discharge (PD) testing is used to detect physical damage of cables, terminations, and joints, contamination on terminations or improper spacing of unshielded parts of terminations that causes tracking, improperly connected, damaged, or corroded metallic shields, electrical trees resulting from water trees, and thermal damage due to overloads. Partial Discharge testing may be performed using very low frequency (VLF) AC test methods.

Any PD in the cable insulation at voltage levels near or slightly above the nominal operating voltage of the cable indicates that cable failure is imminent under normal operating conditions.

When partial discharges are identified, measure and record the Partial Discharge Inception Voltage (PDIV), or the voltage at which point the PD is initiated, and the PD Extinction Voltage (PDEV), or the lower voltage at which point the PD is extinguished, which will help in evaluating the overall condition of the cable, which is a subjective process open to interpretation.

NOTE: One drawback to partial discharge testing is that one location of significant partial discharge can mask areas of lesser PD.

Maintain a record of Partial Discharge test results to track cable electrical characteristics over time.

(This Annex is not a part of the Standard)

Annex B: Reference Standards

This publication, when used in conjunction with the National Electrical Code and manufacturer literature, provides recommended guidelines for commissioning building electrical systems. The following publications may also provide useful information:

National Fire Protection Association
 1 Batterymarch Park
 Quincy, MA 021697471
 (617) 7703000 tel
 (617) 7703500 fax
www.nfpa.org

NFPA 702020, *National Electrical Code* (ANSI)

Institute of Electrical and Electronics Engineers
 445 Hoes Lane
 P.O. Box 1331
 Piscataway, NJ 088551331
 (732) 9810060 tel
 (732) 9819667 fax
www.ieee.org

IEEE 432013, *Recommended Practice for Testing Insulation Resistance of Rotating Machinery*

InterNational Electrical Testing Association
 3050 Old Centre Ave., Suite 102
 Portage, MI 49024
 (888) 300638 tel
 (269) 8886382 tel
 (269) 4886383 fax
www.netaworld.org

[NETA ATS, Standard for Acceptance Testing Specification for Electric Power and Systems \(ANSI\)](#)

[NETA ECS, Standard for Electrical Commissioning Specifications for Electric Power Equipment and Systems](#)

[NETA ETT~~2018~~, Standard for ~~the~~ Certification of Electrical Testing Technicians](#)

[NETA ATS~~2013~~, Standard for Acceptance Testing Specification for Electric Power and Systems \(ANSI\)](#)

National Electrical Contractors Association
 3 Bethesda Metro Center, Suite 1100
 Bethesda, MD 20814
 (301) 6573110 tel
 (301) 2154500 fax

www.necanet.org

Current *National Electrical Installation Standards*[™] published by NECA to be added